





SOIL TEST PIT DATA			
Perc. Test		Observed Groundwater	
Test Date: December 13, 2021 @ 9:10 am Weather: 33°-Sunny/Clear Test Pits: TP#1, TP#2, TP#3 Testing: Eric Dickinson, RS - CIVILIZED SOLUTIONS Witness: Tom Ryder, PE - Ashland BOH Agent Rajit Gupta, RS - Ashland Director of Public Health			
Test Date: October 19, 2022 @ 12:20 pm Weather: 52°-Sunny/Clear Test Pit: TP#4 Testing: Eric Dickinson, RS - CIVILIZED SOLUTIONS Witness: Rajit Gupta, RS - Ashland Director of Public Health			
Test Pit #1	Test Pit #2	Test Pit #3	Test Pit #4
EL. 111.8 2"-0(111.8) 8"(111.1) 18"(110.3) 48"(107.8) 100"(103.5)	EL. 109.0 2"-0(109.0) 6"(108.5) 24"(107.0) 48"(105.0) 100"(100.7)	EL. 110.2 2"-0(110.2) 6"(109.7) 18"(108.7) 24"(108.2) 72"(104.2)	EL. 107.0 2"-0(107.0) 8"(106.3) 16"(105.7) 20"(105.3) 120"(97.0)
Oe Leaves, Sticks, Woods Ap Sandy Loam 10YR3/3 Bw Sandy Loam 10YR4/6 Redox@18" 7.5YR5/8 (strong) & 5Y6/1 C1 Fine Sandy Loam 10YR4/6 compact layer C2 Sandy Loam 2.5Y5/3 weep@72", 20% gravel, roots to 48"	Oe Leaves, Sticks, Woods Ap Sandy Loam 10YR3/3 Bw Sandy Loam 10YR4/6 Redox@24" 7.5YR5/8 wavy bw, roots to 32", weep@48" C Fine Sandy Loam 2.5Y5/3 10% gravel, few cobbles	Oe Leaves, Sticks, Woods Ap Sandy Loam 10YR3/3 Bw Sandy Loam 10YR4/6 Redox@18" 7.5YR5/8 & 5Y6/1 C Fine Sandy Loam 2.5Y5/3 weep@84", 10% gravel, roots to 30"	Oe Leaves, Woods Ap Sandy Loam 10YR3/3 Bw Sandy Loam 10YR4/6 Redox@20" 7.5YR5/8 (strong) C Fine Sandy Loam 2.5Y5/3 weep@84", 5% gravel, cobbles
Class II SCS Class Sandy Loam	Class II SCS Class Sandy Loam	Class II SCS Class Sandy Loam	Class II SCS Class Sandy Loam

PERCOLATION TEST DATA			
Percolation testing could not be performed during the original test date of December 13, 2021 due to groundwater intrusion. Percolation testing was performed on August 10, 2022.			
Test Date: August 10, 2022 @ 8:30 am Weather: 70°-Cloudy/Overcast Test Pit: TP#1 & TP#2 Testing: Eric Dickinson, RS - CIVILIZED SOLUTIONS Witness: Rajit Gupta, RS - Ashland Director of Public Health			
Hole	P-1 (TP#1) (C2-Layer)	P-2 (TP#1) (Bw-Layer)	
Depth (in.)	40"-58"	18"-36"	
Time @ 12"	9:43 am	9:46 am	
Time @ 6"	10:35 am	10:34 am	
Time @ 12"	12:24 pm	11:02 am	
Time (9-6")	109 min.	28 min.	
Rate (Min/")	40 mpi	10 mpi	

I CERTIFY THAT I AM A LICENSED SOIL EVALUATOR (SE #13621), HAVING PASSED THE TRAINING AND TESTING REQUIREMENTS IN APRIL 2013.

ERIC I. DICKINSON DATE: \_\_\_\_\_



**Septic Tank Notes (HD Top):**

- Septic Tank to be LaMarre 1500 FAST with HD top.
- Septic Tank to withstand H-20 loading.
- All pipe connections and concrete construction to be watertight. C.I.P. boots
- Inlet and Outlet tees to be SCH 40 PVC. Tees to be centered under manhole cover.

**Pump Chamber Notes (HD Top):**

- Pump Chamber shall be steel reinforced concrete.
- Pump Chamber to withstand H-20 loading.
- All pipe connections and concrete construction to be watertight. C.I.P. boots
- Inlet and Outlet tees to be SCH 40 PVC. Tees to be centered under manhole cover.
- Recommended manufacturer-Lamarre or approved equivalent.

**Buoyancy Check (HD Tops required on both):**

**Septic Tank (HD TOP Required):**  
 Wgt. of Tank+Soil= 12,000+(10.25x6.15)(1.5)(100)=21,456#  
 Wgt. of Water Displaced= (10.25x6.15)(0.2)(62.4)=787#(OK)

**Pump Chamber (HD TOP Required):**  
 Wgt. of Tank+Soil= 11,000+(8.6x5.0)(1.0)(100)=15,300#  
 Wgt. of Water Displaced= (8.6x5.0)(1.5)(62.4)=4,025#(OK)

**Intensity Regulations (Town of Ashland Zoning Bylaws, Chapter 282, Section 4.0)**  
 Assessors Map 28.0 Block 52  
 Zoned: RESIDENCE A (RA)  
 AREA: 30,000 SF  
 FRONTAGE: 150 FT  
 FRONT SETBACK: 40 FT  
 SIDE YARD SETBACK: 30 FT  
 REAR YARD SETBACK: 30 FT  
 BUILDING HEIGHT: 35 FT

**General Notes:**

- This plan is for the construction of the sewage disposal facility ONLY.
- All pipes shall be SCH 40 PVC or equivalent, unless otherwise noted.
- Contractor shall call for inspections and approvals from the Board of Health and the Engineer after:
  - excavation
  - installation of system components
  - backfilling and final grading
- Engineer shall certify installation and final grades on "As-built" plan. Contractor shall certify that installation conforms to approved As-built plan.
- Prior to final backfill inspection, the contractor shall submit to B.O.H. a sketch with dimensions to system components from building corners and depth to access covers.
- Contractor shall keep vehicles and materials off of the S.A.S. at all times.
- Fill shall not be placed during rain or snow.
- Excavation to be dry and scarified. Dewatering is required if fill is to be placed below groundwater.
- No existing or proposed wells are within 200' of S.A.S., except as shown.
- There are no known public wells or surface water supplies within 400 feet; private wells within 200 feet; inland bays or wetlands within 150 feet; no surface or subsurface drains of any kind except as shown, and no foundation drains. The work area is within the regulatory floodway and the 100-year floodplain.
- Area is Nitrogen Sensitive.
- All system components shall be marked with magnetic marking tape.

**Construction Notes:**

- Within limit of excavation remove the (Oe) Organics, (Ap) topsoil, and other impervious material.
- All construction materials and methods shall conform to D.E.P., Title 5 and the local Board of Health Regulations.
- Contractor shall be responsible for locating any and all underground utilities within the limits of construction. This includes securing and paying for the services of the local utility and private companies to mark all underground utilities on the property. The Engineer does not guarantee that ALL utilities and subsurface structures are shown.
- Sand shall be stockpiled at edge and pushed/cast inward over excavated area.
- Contractor shall install and maintain flagging around the system until the Certificate of Compliance is issued.

**DEED RESTRICTION**

DEED RECORDING - THE PROPOSED SYSTEM HAS BEEN SIZED TO ACCOMMODATE A GARBAGE GRINDER. HOWEVER, IT HAS BEEN SUGGESTED THAT THE USE OF GARBAGE GRINDER CAN HARM THE SYSTEM. THEREFORE, A DEED RESTRICTION PROHIBITING THE USE OF A GARBAGE GRINDER IS REQUIRED PRIOR TO THE ISSUANCE OF A CERTIFICATE OF COMPLIANCE.

NOTE: THE AGENT AND THE SOIL EVALUATOR AGREED THAT THE OBSERVED REDOXIMORPHIC FEATURES BELOW GRADE WERE A CONSERVATIVE INDICATOR OF SEASONAL HIGH GROUNDWATER. THEREFORE, A FRIMPTER ADJUSTMENT IS NOT REQUIRED.



SCALE: 1 INCH = 20 FEET

SCHEDULE OF INVERT ELEVATIONS:	
4" Foundation (Proposed)	109.0
4" F.A.S.T. Tank (IN)	108.7
4" F.A.S.T. Tank (OUT)	108.0
4" Pump Chamber (IN)	107.5
1-1/4" Pump Chamber (OUT)	107.7
5/8" Leaching Pipe (IN)	108.5
5/8" Leaching Pipe (OUT)	110.5
Elev. at Bottom of Excavation	6" B.G.
Observed Groundwater Elev.	36" B.G.
High Groundwater Elev.	18" B.G.
Determination Method	Soil Morphology
B.O.H. Correction Factor	See Note

**SEPTIC SYSTEM CONSTRUCTION**  
 Lot 0 High Street  
 Ashland, Massachusetts

OWNER(S): Charna Daly  
 54 High Street  
 Ashland, MA 01721

ASSESSOR(S):  
 MAP 13.0  
 BLOCK 160.0  
 SHEET 1 OF 2



**DESIGN CRITERIA**

DESIGN FLOW: Single-Family Residence  
 Proposed 3-bedrooms  
 3 Bedrooms @ 110 GPD/Br = 330 GPD  
 \*\*GARBAGE GRINDER IS NOT PERMITTED

**SEPTIC TANK:**  
 Required 330 x 3 = 990 Gal  
 Provided: 1,500 Gal  
 (Use a 2-Compartment, F.A.S.T. Tank)


**LEACHING FACILITY:**  
 Design Perc Rate 40 Min./Inch  
 Soil Class III  
 Loading Rate 0.25 Gal/Day/SF  
 Assume: Geoflow Drip @ 2 SF/LF

**REQUIRED:**  
 330 GPD = 1,320 SF  
 0.25 GPD/SF = 510 GPD/OK  
 (includes 50% increase for garbage grinder)  
 1,320 SF x 150% = 1,980 SF (495 GPD)

**PROVIDED:** 26 ROWS/40 FEET LONG EACH  
 26 x 40.0' x 2' = 2,040 SF (510 GPD)OK

**Revision History**


DESIGNED:	PREPARED BY:
E. Dickinson, RS	CIVILIZED SOLUTIONS
CHECKED:	1102 Highland Street
EID	Holliston, MA 01746
SCALE:	P: 508.429.7192
1"=20'	
DATE:	
Nov. 11, 2022	



**TRADITIONAL SEPTIC DESIGN USING TRENCHES  
PRIMARY AND RESERVE AREA**  
 DESIGN FLOW: Single-Family Residence  
 3 Bedrooms @ 110 GPD/Br = 330 GPD  
 SIZING FOR GARBAGE GRINDER:  
 330 SF x 150% = 495 SF  
 Assume: Six (6) - 2'H x 3'W stone trenches, 48' long.  
 REQUIRED:  
 495 GPD / 0.25 GPD/SF = 1,980 SF  
 PROVIDED LEACHING AREA:  
 6 x 48' x [(2)+(2)+(3)] = 2,016 SF  
 RESERVE LEACHING AREA:  
 6 x 48' x [(2)+(2)+(3)] = 2,016 SF

**GENERAL NOTES**


- 1.) THE WATER SERVICE LOCATION SHOWN IS APPROXIMATE. IF ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE ENGINEER FOR RESOLUTION.
- 2.) ANY SUBSTITUTIONS OF MANUFACTURERS BY THE CONTRACTOR OF THE SEPTIC TANK, PUMP CHAMBER, ETC. SHOWN ON THIS PLAN MUST BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION. PRODUCT CUT SHEETS MUST BE PROVIDED FOR REVIEW.
- 3.) THE CONTRACTOR SHALL CONSULT WITH THE HOMEOWNER PRIOR TO THE REMOVAL OF ANY VEGETATION (TREES, SHRUBS, ETC).
- 4.) A GARBAGE GRINDER NOT PERMITTED BY DESIGN.
- 5.) ALL SYSTEM COMPONENTS SHALL BE MARKED WITH MAGNETIC MARKING TAPE.



**NOTES:**

FULL DUPLEX PANEL SUPPLIED IN A NEMA4X ENCLOSURE.  
 RATED FOR 1PH 115 / 230 (MAX 0.25 HP)  
 CIRCUIT BREAKER PROVIDED FOR PUMP DISCONNECT.  
 PROVIDED WITH MANUAL PUMP CONTROL & PUMP RUN INDICATORS.  
 SEPARATE FUSES FOR ALARM AND CONTROL CIRCUITS.  
 SEPARATE CIRCUITS FOR ALARM & PUMPS.

**VICINITY MAP**



**LEGEND**

- New Meets Existing (N.M.E.)
- L.O.E. Limit of Excavation
- N.I.C. Not In Contract
- Test Pit
- Perc Hole
- Section A-A
- Spot Elevation
- Existing Contour Elevation
- Proposed Contour Elevation
- Groundwater
- Seasonal High Groundwater
- Below Grade
- Tree to be removed

**DESIGN CRITERIA**

DESIGN FLOW: Single-Family Residence  
Proposed 3-bedrooms  
 3 Bedrooms @ 110 GPD/Br = 330 GPD  
 \*\*GARBAGE GRINDER IS NOT PERMITTED

SEPTIC TANK:  
 Required 330 x 3 = 990 Gal  
 Provided: 1,500 Gal  
 (Use a 2-Compartment, F.A.S.T. Tank)

LEACHING FACILITY:  
 Design Perc Rate 40 Min./Inch  
 Soil Class III  
 Loading Rate 0.25 Gal/Day/SF  
 Assume: Geoflow Drip @ 2 SF/LF

REQUIRED:  
 330 GPD / 0.25 GPD/SF = 1,320 SF  
 (includes 50% increase for garbage grinder)  
 1,320 SF x 150% = 1,980 SF (495 GPD)  
 PROVIDED: 26 ROWS/40 FEET LONG EACH  
 26 x 40.0' x 2' = 2,040 SF (510 GPD)(OK)

**SCHEDULE OF INVERT ELEVATIONS:**

4" Foundation (Proposed)	109.0
4" F.A.S.T. Tank (IN)	108.7
4" F.A.S.T. Tank (OUT)	108.0
4" Pump Chamber (IN)	107.5
1-1/4" Pump Chamber (OUT)	107.7
5/8" Leaching Pipe (IN)	108.5
5/8" Leaching Pipe (OUT)	110.5
Elev. at Bottom of Excavation	6" B.G.
Observed Groundwater Elev.	36" B.G.
High Groundwater Elev.	18" B.G.
Determination Method	Soil Morphology
B.O.H. Correction Factor	None

Revision History	December 16, 2022 - Conservation Agent comments
DESIGNED: E. Dickinson, RS	PREPARED BY:
CHECKED: EID	<i>CIVILized Solutions</i>
SCALE: 1"=20'	1102 Highland Street Holliston, MA 01746 P: 508.429.7192
DATE: Nov. 11, 2022	

SEPTIC SYSTEM CONSTRUCTION Lot 0 High Street Ashland, Massachusetts	
OWNER(S): Charna Daly 54 High Street Ashland, MA 01721	ASSESSOR(S): MAP 13.0 BLOCK 160.0
SHEET 2 OF 2	