



1 International Blvd
Suite 800
Mahwah, NJ 07495

STRUCTURAL ANALYSIS
BS23XC490



Address:

396 CEDAR STREET
ASHLAND, MA 01721

Date:

MAY 14, 2018



May 14, 2018

Sprint
15 Commerce Way
Suite B
Norton, MA 02766

RE:

Site Number: BS23XC490
Site Name: Cedar Street Water Tank
Site Address: 396 Cedar Street, Ashland, MA 01721

To whom it may concern:

Chappell Engineering Associates, LLC has performed a structural analysis of the existing Sprint antenna mounts located on the above-referenced water tank at approximately 80ft AGL.

The existing antenna mounts consist of six (6) stud-welded antenna mounting assemblies (2 per sector, total of 3 sectors) secured to the existing water tank face. Two (2) stand-off mounts are used per antenna pipe connection with each stand-off mounts utilizing eight (8) 5/16" studs. Our analysis has considered the following total major equipment loads indicated on the antenna design summary (included in this report) to be installed on the existing antenna mounting frames:

| Sectors | Status | Antenna/RRH | Dimensions (in) | Location |
|--------------------|----------|--------------------------|-----------------------|-----------------------|
| Alpha, Beta, Gamma | Proposed | (1) CommScope DT465B-2XR | 71.9H x 13.8W x 8.2D | Mounted to Water Tank |
| | Proposed | (1) ALU RRH 800MHz | 21.1H x 13.8W x 16.8D | Mounted to Water Tank |
| | Proposed | (1) ALU RRH 2500MHz | 26.1H x 18.6W x 6.7D | Mounted to Water Tank |
| | Existing | (1) RFS APXVSP18-C | 72.0H x 11.8W x 7.0D | Mounted to Water Tank |
| | Existing | (1) ALU RRH 800MHz | 21.1H x 13.8W x 16.8D | Mounted to Water Tank |
| | Existing | (1) ALU RRH 1900MHz | 26.0H x 14.0W x 15.0D | Mounted to Water Tank |

Additionally, since the existing antenna mounting pipes currently support a single AT&T antenna and Ericsson RRU, we have included the AT&T antenna and RRU in our analysis of the existing mount. For additional mast stability the existing upper free end of the antenna support mast shall be braced back to the tank dome. Proposed 3"x3"x1/4" angles will be added attached to the existing antenna mounting pipes & tied back to the water tank as shown on the construction drawings.

We have performed an analysis of the antenna mounting pipe and stud weld connections to verify the existing mounts can support the proposed loads shown above.

Photos of the existing antennas/RRHs and the proposed locations of the new antennas/RRHs and bracing are enclosed for your convenience. A copy of the DO Macro upgrade construction drawings detail the additional bracing L's and connections. Our analysis and results are also included in this report. Based upon our analysis of the proposed antenna mounts, the information obtained from our site visit, and the magnitude of the anticipated loads, we consider the proposed antenna mounts, **once reinforced with the additional bracing angles will have adequate capacity** to support the proposed antenna configuration as shown on the construction drawings.

If you have any questions regarding this matter, please do not hesitate to call.

Very truly yours,
CHAPPELL ENGINEERING ASSOCIATES, LLC


Clement J. Salek, P.E.
CJS/ajs



Appendix A – RF Antenna Data Sheets

| | | | | | |
|--|--|--|----------------------------|--|---|
| Site Data | Market: | Boston | | Revision 2.0 | Rev Date: 4-Aug-2017 |
| | Cascade ID | BS23XC490 | | BTS OEM: ALU | RFDS Type: Preliminary |
| | Augment Import Code: SPDOMU01_DO_Macro_Upgrade | Augment: DO Macro Upgrade | | | |
| | Address: 396 Cedar Street, Ashland, MA, 01721 Latitude: 42.23533599 Longitude: -71.43961716 | Sprint Eng. Name: Bill Hastings Manager Name: Jonathan Hull | | Bill.M.Hastings@sprint.com Jonathan.B.Hull@sprint.com | Eng. Phone: 978-590-9700 Manager Phone: 617-233-2920 |
| Detailed RFDS Description: | RFE: Praveen Meesarapu | Praveen.Meesarapu@sprint.com | | RFE Phone: 301-728-0006 | |
| Triband final config using NV + 800/2.5 dual band antenna. Adding 2nd 800 RRH and 2.5 RRH | Filter Analysis Complete: YES | Border Analysis Complete: YES | Channel Plan Complete: YES | | |
| | Alpha | Beta | Gamma | | |
| 1900MHz_Azimuth | 10 | 170 | 270 | | |
| 1900MHz_No_of_Antennas | 1 | 1 | 1 | | |
| 1900MHz_RADCenter(ft) | 80.2 | 80.2 | 80.2 | | |
| 1900MHz_Antenna_Make | RFS | RFS | RFS | | |
| 1900MHz_Antenna_Model | APXVSP18-C-A20 | APXVSP18-C-A20 | APXVSP18-C-A20 | | |
| 1900MHz_Horizontal_Beamwidth | 65 | 65 | 65 | | |
| 1900MHz_Vertical_Beamwidth | 6 | 6 | 6 | | |
| 1900MHz_Antenna_Dimensions (ft) & Weight (lbs) | 72 x 11.8 x 7.9 28 (lbs) | 72 x 11.8 x 7.9 28 (lbs) | 72 x 11.8 x 7.9 28 (lbs) | | |
| 1900MHz_AntennaGain(dBi) | 18 | 18 | 18 | | |
| 1900MHz_E_Tilt | 0 | 0 | 0 | | |
| 1900MHz_M_Tilt | 0 | 0 | 0 | | |
| 1900_Effective_Tilt | 0 | 0 | 0 | | |
| 1900MHz_Carrier_Forecast_Year_2017 | | | | | |
| 1900MHz_RRH_Manufacturer | ALU | ALU | ALU | | |
| 1900MHz_RRH_Model | RRH 1900 4X45 65MHz | RRH 1900 4X45 65MHz | RRH 1900 4X45 65MHz | | |
| 1900MHz_RRH_Count | 1 | 1 | 1 | | |
| 1900MHz_RRH_Specs | 25 x 11.1 x 11.4 (60 lbs) | 25 x 11.1 x 11.4 (60 lbs) | 25 x 11.1 x 11.4 (60 lbs) | | |
| 1900MHz_RRH_Location | Top of the Pole/Tower | Top of the Pole/Tower | Top of the Pole/Tower | | |
| 1900MHz_Combiner_Model | No Combiner Required | No Combiner Required | No Combiner Required | | |
| 1900MHz_Power_Split_Ratio (Main/Split) | | | | | |
| 1900MHz_Splitter_Manufacturer | | | | | |
| 1900MHz_Splitter_Model | No Splitter Required | No Splitter Required | No Splitter Required | | |
| 1900MHz_Number_of_Splitters | 0 | 0 | 0 | | |
| 1900MHz_Top_Jumper #1_Length (RRH or Combiner-to-Antenna for TT or Main Coax to Antenna for Ground Mount, ft) | 8 | 8 | 8 | | |
| 1900MHz_Top_Jumper #1_Cable_Model (RRH or Combiner-to-Antenna for TT or Main Coax to Antenna for Ground Mount) | LCF12-50J | LCF12-50J | LCF12-50J | | |
| 1900MHz_Top_Jumper #2_Length (RRH to Combiner for TT if applicable, ft) | | | | | |
| 1900MHz_Top_Jumper #2_Cable_Model (RRH to Combiner for TT if applicable) | | | | | |
| 1900MHz_Main_Cable_Length (ft) | 105.2 | 105.2 | 105.2 | | |
| 1900MHz_Main_Cable_Model | Hyberflex Cable | Hyberflex Cable | Hyberflex Cable | | |
| 1900MHz_Bottom_Jumper #1_Length (Ground based RRH to Combiner-OR-Main Coax, ft) | | | | | |
| 1900MHz_Bottom_Jumper #1_Cable_Model (Ground based RRH to Combiner-OR-Main Coax) | | | | | |
| 1900MHz_Bottom_Jumper #2_Length (Ground based-Combiner to Main Coax, ft) | | | | | |
| 1900MHz_Bottom_Jumper #2_Cable_Model (Ground based-Combiner to Main Coax) | | | | | |
| 1900 | | | | | |

| | | | | | |
|--|---|--------------------------------------|--------------------------------------|--------------------------------------|-----------|
| 800 | 800MHz_Azimuth | 10 | 170 | 270 | |
| | 800MHz_No_of_Antennas | 1 | 1 | 1 | |
| | 800MHz_RADCenter(ft) | 80.2 | 80.2 | 80.2 | |
| | 800MHz_AntennaMake | NA | NA | NA | |
| | 800MHz_AntennaModel | Antenna assigned on a different band | Antenna assigned on a different band | Antenna assigned on a different band | |
| | 800MHz_Horizontal_Beamwidth | NA | NA | NA | |
| | 800MHz_Vertical_Beamwidth | NA | NA | NA | |
| | 800MHz_Antenna_Dimensions (ft) & Weight (lbs) | NA NA | NA NA | NA NA | |
| | 800MHz_AntennaGain (dBd) | NA | NA | NA | |
| | 800MHz_E_Tilt | 0 | 0 | 0 | |
| | 800MHz_M_Tilt | 0 | 0 | 0 | |
| | 800 MHz_Effective Tilt (degrees) | 0 | 0 | 0 | |
| | 800MHz_RRH_Manufacturer | ALU | ALU | ALU | |
| | 800_Combiner_Model | No Combiner Required | No Combiner Required | No Combiner Required | |
| | 800MHz_RRH_Model | RRH 800 MHz 2x50W | RRH 800 MHz 2x50W | RRH 800 MHz 2x50W | |
| | 800MHz_RRH_Specs | 15.8 x 13 x 14 (64 lbs) | 15.8 x 13 x 14 (64 lbs) | 15.8 x 13 x 14 (64 lbs) | |
| | 800MHz_RRH_Count | 2 | 2 | 2 | |
| | 800MHz_RRH_Location | Top of the Pole/Tower | Top of the Pole/Tower | Top of the Pole/Tower | |
| | 800MHz_Power_Split_Ratio (Main/Split) | | | | |
| | 800MHz_Splitter_Manufacturer | | | | |
| | 800MHz_Splitter_Model | | | | |
| | 800MHz_Number_of_Splitters | 0 | 0 | 0 | |
| | 800_Top_Jumper #1_Length (RRH to Antenna for TT or Main Coax to Antenna for GM) | 8 | 8 | 8 | |
| | 800_Top_Jumper_Cable_Model (RRH to Antenna for TT or Main Coax to Antenna for GM) | LCF12-50J | LCF12-50J | LCF12-50J | |
| | 800MHz_Main_Coax_Cable_Length (ft) | NA | NA | NA | |
| | 800MHz_Main_Coax_Cable_Model | NA | NA | NA | |
| | 800_Bottom_Jumper #1_Length (Ground based RRH to Main Coax) | | | | |
| | 800_Bottom_Jumper #1_Cable_Model (Ground based RRH to Main Coax) | | | | |
| | 2500 | 2500MHz_Azimuth | 10 | 170 | 270 |
| | | 2500MHz_No_of_Antennas | 1 | 1 | 1 |
| | | 2500MHz_RADCenter(ft) | 80.2 | 80.2 | 80.2 |
| | | 2500MHz_AntennaMake | Commscope | Commscope | Commscope |
| 2500MHz_AntennaModel | | DT465B-2XR | DT465B-2XR | DT465B-2XR | |
| 2500MHz_Horizontal_Beamwidth | | 68 | 68 | 68 | |
| 2500MHz_Vertical_Beamwidth | | 4.3 | 4.3 | 4.3 | |
| 2500MHz_AntennaHeight (ft) | | 72 x 13.8 x 8.2 58 (lbs) | 72 x 13.8 x 8.2 58 (lbs) | 72 x 13.8 x 8.2 58 (lbs) | |
| 2500MHz_AntennaGain (dBd) | | 17.5 | 17.5 | 17.5 | |
| 2500MHz_E_Tilt | | 0 | -1 | 0 | |
| 2500MHz_M_Tilt | | 0 | 0 | 0 | |
| 2500 MHz_Effective Tilt (degrees) | | 0 | -1 | 0 | |
| 2500MHz_RRH_Manufacturer | | ALU | ALU | ALU | |
| 2500_Combiner_Model | | No Combiner Required | No Combiner Required | No Combiner Required | |
| 2500MHz_RRH_Model | | TD-RRH8x20-25 | TD-RRH8x20-25 | TD-RRH8x20-25 | |
| 2500MHz_RRH_Count | | 1 | 1 | 1 | |
| 2500MHz_RRH_Location | | Top of the Pole/Tower | Top of the Pole/Tower | Top of the Pole/Tower | |
| 2500MHz_Power_Split_Ratio (Main/Split) | | | | | |
| 2500MHz_Splitter_Manufacturer | | | | | |
| 2500MHz_Splitter_Model | | | | | |
| 2500MHz_Number_of_Splitters | | 0 | 0 | 0 | |
| 2500_Top_Jumper #1_Length (RRH to Antenna for TT or Main Coax to Antenna for GM) | | 8 | 8 | 8 | |
| 2500_Top_Jumper_Cable_Model (RRH to Antenna for TT or Main Coax to Antenna for GM) | | LCF12-50J | LCF12-50J | LCF12-50J | |
| 2500MHz_Main_Cable_Length (ft) | | 105.2 | | | |
| 2500MHz_Main_Cable_Model | | Hyberflex Cable | | | |
| 2500_Bottom_Jumper #1_Length (Ground based RRH to Main Coax) | | | | | |
| 2500_Bottom_Jumper #1_Cable_Model (Ground based RRH to Main Coax) | | | | | |
| Comments | Has_Split | No | No | No | |
| | Plumbing_Scenario | Option B | Option B | Option B | |
| | Date_Updated | | | | |
| | Update_Description | | | | |
| | Site_Type | | | | |
| | Comments | | | | |
| This RFDS is Deployment View | | | | | |

Appendix B – Construction Drawings

SPECIAL CONSTRUCTION NOTE:
 SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
 * COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY TOWER OWNER OR A&E VENDOR).
 * COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).
 * GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.



NOTE:
 OWNER AND TENANT MAY, FROM TIME TO TIME AT TENANT'S OPTION, REPLACE THIS EXHIBIT WITH AN EXHIBIT SETTING FORTH THE LEGAL DESCRIPTION OF THE SITE, OR WITH ENGINEERED OR AS-BUILT DRAWING DEPICTING THE SITE OR ILLUSTRATING STRUCTURAL MODIFICATIONS OR CONSTRUCTION PLANS OF THE SITE. ANY VISUAL OR TEXTUAL REPRESENTATION OF THE EQUIPMENT LOCATED WITHIN THE SITE CONTAINED IN THESE OTHER DOCUMENTS IS ILLUSTRATIVE ONLY AND DOES NOT LIMIT THE RIGHTS OF SPRINT AS PROVIDED FOR IN THE AGREEMENT. THE LOCATIONS OF ANY ACCESS AND UTILITY EASEMENTS ARE ILLUSTRATIVE ONLY. ACTUAL LOCATIONS MAY BE DETERMINED BY TENANT AND/OR THE SERVICING UTILITY COMPANY IN COMPLIANCE WITH LOCAL LAWS AND REGULATIONS.

PROJECT: DO MACRO UPGRADE
SITE NAME: CEDAR ST. WATER TANK
SITE CASCADE: BS23XC490
SITE ADDRESS: 396 CEDAR STREET
 ASHLAND, MA 01721
SITE TYPE: 90' TALL WATER TANK



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

CHECKED BY: JMT

APPROVED BY: JMT

| SUBMITTALS | | | |
|------------|----------|-------------------------|-----|
| REV. | DATE | DESCRIPTION | BY |
| 3 | 06/09/18 | ISSUED FOR CONST. FINAL | CMC |
| 2 | 01/10/18 | ISSUED FOR CONSTRUCTION | CMF |
| 1 | 10/21/17 | ISSUED FOR CONSTRUCTION | SDU |
| 0 | 09/29/17 | ISSUED FOR REVIEW | SDU |

SITE NUMBER:
BS23XC490
 SITE NAME:
CEDAR ST. WATER TANK
 SITE ADDRESS:
 396 CEDAR STREET
 ASHLAND, MA 01721

SHEET TITLE
TITLE SHEET

SHEET NUMBER
T-1

SITE INFORMATION

PROPERTY OWNER:

TOWN OF ASHLAND
 101 MAIN STREET
 ASHLAND, MA 01721

LATITUDE (NAD83):

GOOGLE EARTH 2-C CONFIRMATION

N 42° 14' 07.20"
 N 42.2353°

LONGITUDE (NAD83):

GOOGLE EARTH 2-C CONFIRMATION

W -71° 26' 23.16"
 W -71.4398°

COUNTY:

MIDDLESEX

ZONING JURISDICTION:

TOWN OF ASHLAND

ZONING DISTRICT:

RESIDENTIAL A

POWER COMPANY:

NSTAR
 PHONE: 1-800-592-2000

AAV PROVIDER:

COMCAST
 PHONE: 1-800-COMCAST

SPRINT CM:

RONALD FARIAS
 PHONE: 617-247-4303
 Ronald.Farias@sprint.com

EQUIPMENT SUPPLIER:


ALCATEL-LUCENT
 600 MOUNTAIN AVENUE
 MURRAY HILL, NJ 07974
 (908) 508-8080

NOTE:
 THE CONTRACTOR SHALL HAVE A FIELD SUPERVISOR AT THE SITE TO ATTEND PRECONSTRUCTION MEETING. AT THE END OF EACH WORK DAY, THE CONTRACTOR SHALL PREPARE A GENERAL DESCRIPTION REPORT OF THAT DAY'S WORK PERFORMED WITH APPROPRIATE PHOTOGRAPHS OF WORK ITEMS. REPORT TO BE EMAILED TO HALEY AND WARD PROJECT MANAGER.

AREA MAP



LOCATION MAP - GOOGLE EARTH 2-C CONFIRMATION



PROJECT DESCRIPTION

SPRINT EQUIPMENT MODIFICATIONS REQUIRED TO SUPPORT MODERNIZATION OF AN EXISTING WIRELESS COMMUNICATIONS FACILITY AND UTILIZATION OF FCC BROADBAND SPECTRUM LICENSE FOR 2.5GHZ FREQUENCY, INCLUDING INSTALLATION OF:

- GROUND-LEVEL RAN EQUIPMENT, CONSISTING OF
- (1) NEW 2.5GHZ RETROFIT KIT IN EXISTING MMBTS CABINET IN EXISTING SHELTER
 - (1) ADDITIONAL BATTERY STRING(S) INSIDE EXISTING BATTERY BACKUP (BBU) CABINET
 - (1) ADDITIONAL RECTIFIER SHELF AND RECTIFIERS INSIDE EXISTING SPRINT MMBTS CABINET AS REQUIRED

TOWER-TOP EQUIPMENT, INCLUDING INSTALLATION OF:

- (3) PANEL ANTENNAS
- (6) REMOTE RADIO HEADS (RRH)
- (3) HYBRID (FIBER & POWER) CABLE (AND ASSOCIATED FIBER, DC POWER, COAXIAL CABLE JUMPERS AND ANTENNA REMOTE ELECTRICAL-TILT (RET) CABLE

SPECIAL ZONING NOTE:

BASED ON INFORMATION PROVIDED BY SPRINT REGULATORY COMPLIANCE PROFESSIONALS AND LEGAL COUNSEL, THIS TELECOMMUNICATIONS EQUIPMENT DEPLOYMENT IS CONSIDERED AN ELIGIBLE FACILITY UNDER THE TAX RELIEF ACT OF 2012, 47 USC 1455(A), AND IS SUBJECT TO AN EXPEDITED ELIGIBLE FACILITIES REQUEST/REVIEW AND ZONING PRE-EMPTION FOR LOCAL DISCRETIONARY PERMITS (VARIANCE, SPECIAL PERMIT, SITE PLAN REVIEW, ADMINISTRATIVE REVIEW).

GENERAL NOTES

- THIS IS AN UNMANNED AND RESTRICTED ACCESS TELECOMMUNICATION FACILITY, AND IS NOT FOR HUMAN HABITATION. IT WILL BE USED FOR THE TRANSMISSION OF RADIO SIGNAL FOR THE PURPOSE OF PROVIDING PUBLIC CELLULAR SERVICE.
 - ADA COMPLIANCE NOT REQUIRED.
 - PORTABLE WATER OR SANITARY SERVICE IS NOT REQUIRED.
 - NO OUTDOOR STORAGE OR ANY SOLID WASTE RECEPTACLES REQUIRED.
- CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON JOB SITE. CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ARCHITECT/ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK. FAILURE TO NOTIFY THE ARCHITECT/ENGINEER PLACE THE RESPONSIBILITY ON THE CONTRACTOR TO CORRECT THE DISCREPANCIES AT THE CONTRACTOR'S EXPENSE.
- NEW CONSTRUCTION WILL CONFORM TO ALL APPLICABLE CODES AND ORDINANCES.
 - BUILDING CODE: MASSACHUSETTS STATE BUILDING CODE 780 CRM-8TH EDITION
 - ELECTRICAL CODE: 2005 NATIONAL ELECTRICAL CODE
 - STRUCTURAL CODE: TIA/EIA-222-G STRUCTURAL STANDARDS FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS.

AT LEAST 72 HOURS PRIOR TO DIGGING, THE CONTRACTOR IS REQUIRED TO CALL DIG SAFE AT 811



DRAWING INDEX

| SHEET NO. | SHEET TITLE | REV. | CHK. | BY. |
|-----------|--------------------------------|------|------|-----|
| T-1 | TITLE SHEET | 3 | JMT | CAW |
| SP-1 | OUTLINE SPECIFICATIONS | 3 | JMT | CAW |
| SP-2 | OUTLINE SPECIFICATIONS | 3 | JMT | CAW |
| SP-3 | OUTLINE SPECIFICATIONS | 3 | JMT | CAW |
| A-1 | COMPOUND & EQUIPMENT PLAN | 3 | JMT | CAW |
| A-2 | ELEVATION & ANTENNA PLANS | 3 | JMT | CAW |
| A-3 | RF DATA SHEET | 3 | JMT | CAW |
| A-4 | RAN WIRING DIAGRAMS | 3 | JMT | CAW |
| A-5 | EQUIPMENT DETAILS | 3 | JMT | CAW |
| A-6 | EQUIPMENT DETAILS | 3 | JMT | CAW |
| S-1 | STRUCTURAL DETAILS | 3 | JMT | CAW |
| E-1 | ONE-LINE DIAGRAM & PPC DETAILS | 3 | JMT | CAW |
| E-2 | GROUNDING DETAILS & NOTES | 3 | JMT | CAW |

APPROVALS

THE FOLLOWING PARTIES HEREBY APPROVE AND ACCEPT THESE DOCUMENTS AND AUTHORIZE THE CONTRACTOR TO PROCEED WITH THE CONSTRUCTION DESCRIBED HEREIN. ALL DOCUMENTS ARE SUBJECT TO REVIEW BY THE LOCAL BUILDING DEPARTMENT AND MAY IMPOSE CHANGES OR MODIFICATIONS.

SPRINT: _____ DATE: _____
 CONSTRUCTION MANAGER: _____ DATE: _____
 LEASING/ SITE ACQUISITION: _____ DATE: _____
 RF ENGINEER: _____ DATE: _____
 LANDLORD/ TOWER OWNER: _____ DATE: _____

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 - SCOPE OF WORK

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.

1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:

- A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 - 1. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT
 - 2. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 - 3. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
 - 4. AMERICAN SOCIETY OF TESTING OF MATERIALS (ASTM)
 - 5. INSTITUTE OF ELECTRIC AND ELECTRICAL ENGINEERS (IEEE)
 - 6. AMERICAN CONCRETE INSTITUTE (ACI)
 - 7. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 - 8. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 - 9. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (ASHTO)
 - 10. PORTLAND CEMENT ASSOCIATION (PCA)
 - 11. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 - 12. BRICK INDUSTRY ASSOCIATION (BIA)
 - 13. AMERICAN WELDING SOCIETY (AWS)
 - 14. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 - 15. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 - 16. DOOR AND HARDWARE INSTITUTE (DHI)
 - 17. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 - 18. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS:

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFFIC: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...
- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
 - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
 - B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
 - C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED.
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.
 - A. TOP HAT
 - B. HOW TO INSTALL A NEW CABINET
 - C. BASE BAND UNIT IN EXISTING UNIT
 - D. INSTALLATION OF BATTERIES
 - E. INSTALLATION OF HYBRID CABLE
 - F. INSTALLATION OF RRH'S
 - G. CABLING
 - H. TS-0200 REV 4 - ANTENNA LINE ACCEPTANCE STANDARDS
 - I. SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1.
 - J. COMMISSIONING MOPS
 - K. SPRINT CELL SITE ENGINEERING NOTICE - EN-2013-002
 - L. SPRINT ENGINEERING LETTER - EL-0504
 - M. SPRINT ENGINEERING LETTER - EL-0568
 - N. SPRINT TECHNICAL SPECIFICATION - TS-0193
- 1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:
 - A. CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT SYSTEMS. CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET ACCESS, EQUIVALENT TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTOR'S STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING; REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.
- 3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
 - A. COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
 - B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 - 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 - 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
- 3.2 DELIVERABLES:
 - A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
 - B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
 - C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 - CELL SITE CONSTRUCTION

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.
- 1.3 NOTICE TO PROCEED:
 - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
 - B. TOWER OWNER NOTIFICATION: ONCE THE CONTRACTOR HAS RECEIVED AND ACCEPTED THE NOTICE TO PROCEED, THE CONTRACTOR WILL CONTACT THE CONSTRUCTION MANAGER OF RECORD (NOTED ON THE FIRST PAGE ON THIS CONSTRUCTION DRAWING) A MINIMUM OF 48 HOURS PRIOR TO WORK START. UPON ARRIVAL TO THE JOB SITE, CONTRACTOR CREW IS REQUIRED TO CALL TO NOTIFY THE WORK HAS BEGUN.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 FUNCTIONAL REQUIREMENTS:
 - A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
 - B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
 - C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
 - D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - 1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
 - 2. PREPARE GROUND STIES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
 - 3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
 - 4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
 - 5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
 - 6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
 - 7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
 - 8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
 - 9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
 - 10. ABATE OR ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
 - 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
 - 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
 - 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
 - 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.
 - 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
 - 16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
 - 17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
 - 18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY PERMITTING AGENCIES AND LANDLORDS.
 - 19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
 - 20. REMAIN ON-SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."
- 3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:
 - A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
 - B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED 'BROOM CLEAN' AND CLEAR OF DEBRIS.
 - C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
 - 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN IDENTIFIED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
 - 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
 - D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
 - E. CONDUCT TESTING AS REQUIRED HEREIN.
- 3.3 DELIVERABLES:
 - A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
 - B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 - 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 - 2. PROJECT PROGRESS REPORTS.
 - 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

CONTINUE SHEET SP-2



1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
(800) 357-7641



CENTERLINE COMMUNICATIONS
95 RYAN DRIVE, SUITE 1
RAYNHAM, MA 02767



R.R. EXECUTIVE CENTRE
201 BOSTON POST ROAD WEST, SUITE 101
MAHAROUGH, MA 01752
(508) 481-7400
www.chappellengineering.com



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

CHECKED BY: JMT

APPROVED BY: JMT

| SUBMITTALS | | | |
|------------|----------|-------------------------|-----|
| REV. | DATE | DESCRIPTION | BY |
| 3 | 06/09/18 | ISSUED FOR CONST. FINAL | CJC |
| 2 | 01/10/18 | ISSUED FOR CONSTRUCTION | CJC |
| 1 | 10/21/17 | ISSUED FOR CONSTRUCTION | BDU |
| 0 | 08/29/17 | ISSUED FOR REVIEW | BDU |

SITE NUMBER:
BS23XC490
SITE NAME:
CEDAR ST. WATER TANK
SITE ADDRESS:
386 CEDAR STREET
ASHLAND, MA 01721

SHEET TITLE
OUTLINE SPECIFICATIONS
SHEET NUMBER
SP-1

CONTINUED FROM SP-1:

- 12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
- 13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS, TESTS, AND INSPECTIONS

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.

1.3 SUBMITTALS:

- A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
- B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
 - 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 - 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 - 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 - 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 - 5. CHEMICAL GROUNDING DESIGN.
- C. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - 1. COAX SWEEPS AND FIBER TESTS PER SPRINT TS-0200 CURRENT VERSION ANTENNA LINE ACCEPTANCE STANDARDS.
 - 2. AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 - 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 - 1. AZIMUTH, DOWNTILT, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
 - 2. SCANNABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 - 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
 - 4. PDF SCAN OF REDLINES PRODUCED IN FIELD
 - 5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
 - 6. LIEN WAIVERS
 - 7. FINAL PAYMENT APPLICATION
 - 8. REQUIRED FINAL CONSTRUCTION PHOTOS
 - 9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
 - 10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPS

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPS

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY: WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.

- 1. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
- 2. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.
- 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

- A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - 1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 - 2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
 - 3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 - 4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
 - 5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.

- 6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
- 7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
- 8. GROUND AND ANTENNA MASTS FOR GPS AND ANTENNAS
- 9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS:

- A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - 1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 - 2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 - 3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 - 4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
 - 5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
 - 6. ANTENNA AZIMUTH , DOWN TILT AND PER SUNLIGHT TOOL SUNSHINE INSTRUMENTS - INTENNALIGN ALIGNMENT TOOL (AAT)
 - 7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
 - 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC.). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
 - 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
 - 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 - 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
 - 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- E. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- F. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.

3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.

A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.

- 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
- 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
- 3. SITE RESISTANCE TO EARTH TEST.
- 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
- 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
- 6. COAX CABLE SWEEP TESTS PER COMPANY'S ANTENNA LINE ACCEPTANCE STANDARDS.

B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING:

- 1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
- 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING.
- 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
- 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
- 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF.
- 6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
- 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
- 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL AND ASPHALT PAVING MIX DESIGN.
- 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 500 - PROJECT REPORTING

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 WEEKLY REPORTS:

- A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORM WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
- B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

3.2 PROJECT CONFERENCE CALLS:

- A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

3.3 PROJECT TRACKING IN SMS:

- A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.

3.4 ADDITIONAL REPORTING:

- A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.

3.5 PROJECT PHOTOGRAPHS:

- A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
 - 1. SHELTER AND TOWER OVERVIEW.
 - 2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
 - 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
 - 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
 - 5. PHOTOS OF TOWER SECTION STACKING.
 - 6. CONCRETE TESTING / SAMPLES.
 - 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
 - 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
 - 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
 - 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
 - 11. COAX CABLE ENTRY INTO SHELTER.
 - 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 - 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
 - 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
 - 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
 - 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
 - 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
 - 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
 - 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 - 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
 - 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 - 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 - 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 - 24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 - 25. ALL BTS GROUND CONNECTIONS.
 - 26. ALL GROUND TEST WELLS.
 - 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
 - 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
 - 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
 - 30. GPS ANTENNAS.
 - 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
 - 32. DOGHOUSE/CABLE EXIT FROM ROOF.
 - 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
 - 34. MASTER BUS BAR
 - 35. TELCO BOARD AND NIU.
 - 36. ELECTRICAL DISTRIBUTION WALL.
 - 37. CABLE ENTRY WITH SURGE SUPPRESSION.
 - 38. ENTRANCE TO EQUIPMENT ROOM.
 - 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
 - 40. COAX GROUNDING -TOP AND BOTTOM OF TOWER.
 - 41. ANTENNA AND MAST GROUNDING.
 - 42. LANDSCAPING - WHERE APPLICABLE.

3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERA.

SECTION 07 500 - ROOF CUTTING, PATCHING AND REPAIR

SUMMARY: THIS SECTION SPECIFIES CUTTING AND PATCHING EXISTING ROOFING SYSTEMS WHERE CONDUIT OR CABLES EXIT THE BUILDING ONTO THE ROOF OR BUILDING-MOUNTED ANTENNAS, AND AS REQUIRED FOR WATERTIGHT PERFORMANCE. ROOFTOP ENTRY OPENINGS IN MEMBRANE ROOFTOPS SHALL BE CONSTRUCTED TO COMPLY WITH LANDLORD, ANY EXISTING WARRANTY, AND LOCAL JURISDICTIONAL STANDARDS.

1.4 SUBMITTALS:

- A. PRE-CONSTRUCTION ROOF PHOTOS: COMPLETE A ROOF INSPECTION PRIOR TO THE INSTALLATION OF SPRINT EQUIPMENT ON ANY ROOFTOP BUILD. AT A MINIMUM INSPECT AND PHOTOGRAPH (MINIMUM 3 EA.) ALL AREAS IMPACTED BY THE ADDITION OF THE SPRINT EQUIPMENT.
- B. PROVIDE SIMILAR PHOTOGRAPHS SHOWING ROOF CONDITIONS AFTER CONSTRUCTION (MINIMUM 3 EA.)
- C. ROOF INSPECTION PHOTOGRAPHS SHOULD BE UPLOADED WITH CLOSEOUT PHOTOGRAPHS.



1 INTERNATIONAL BLVD, SUITE 800
 MAHWAH, NJ 07495
 (800) 357-7641

CENTERLINE COMMUNICATIONS
 95 RYAN DRIVE, SUITE 1
 RAYNHAM, MA 02767

CHAPPELL ENGINEERING ASSOCIATES, LLC
 Civil/Structural/Land Surveying

R.K. EXECUTIVE CENTRE
 201 BOSTON POST ROAD WEST, SUITE 101
 MAHARJOUR, MA 01752
 (508) 481-7400
 www.chappellengineering.com



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

CHECKED BY: JMT
 APPROVED BY: JMT

| SUBMITTALS | | | |
|------------|----------|-------------------------|-----|
| REV. | DATE | DESCRIPTION | BY |
| 3 | 06/09/18 | ISSUED FOR CONST. FINAL | CMC |
| 2 | 01/10/18 | ISSUED FOR CONSTRUCTION | CMC |
| 1 | 10/26/17 | ISSUED FOR CONSTRUCTION | GBU |
| 0 | 09/20/17 | ISSUED FOR REVIEW | GBU |

SITE NUMBER:
BS23XC490

SITE NAME:
CEDAR ST. WATER TANK

SITE ADDRESS:
 386 CEDAR STREET
 ASHLAND, MA 01721

SHEET TITLE
OUTLINE SPECIFICATIONS

SHEET NUMBER
SP-2

CONTINUED FROM SP-2:
SECTION 09 900 - PAINTING
QUALITY ASSURANCE:

- A. COMPLY WITH GOVERNING CODES AND REGULATIONS. PROVIDE PRODUCTS OF ACCEPTABLE MANUFACTURERS WHICH HAVE BEEN IN SATISFACTORY USE IN SIMILAR SERVICE FOR THREE YEARS. USE EXPERIENCED INSTALLERS. DELIVER, HANDLE, AND STORE MATERIALS IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
- B. COMPLY WITH ALL ENVIRONMENTAL REGULATIONS FOR VOLATILE ORGANIC COMPOUNDS.
- MATERIALS:**
- A. MANUFACTURERS: BENJAMIN MOORE, ICI DEVCOE COATINGS, PPG, SHERWIN WILLIAMS OR APPROVED EQUAL. PROVIDE PREMIUM GRADE, PROFESSIONAL-QUALITY PRODUCTS FOR COATING SYSTEMS.

- PAINT SCHEDULE:**
- A. EXTERIOR ANTENNAE AND ANTENNA MOUNTING HARDWARE: ONE COAT OF PRIMER AND TWO FINISH COATS. PAINT FOR ANTENNAE SHALL BE NON-METALLIC BASED AND CONTAIN NO METALLIC PARTICLES. PROVIDE COLORS AND PATTERNS AS REQUIRED TO MASK APPEARANCE OF ANTENNAE ON ADJACENT BUILDING SURFACES AND AS ACCEPTABLE TO THE OWNER. REFER TO ANTENNA MANUFACTURER'S INSTRUCTIONS WHENEVER POSSIBLE.

- B. **ROOF TOP CONSTRUCTION:** TOUCH UP - PREPARE SURFACES TO BE REPAIRED. FOLLOW INDUSTRY STANDARDS AND REQUIREMENTS OF OWNER TO MATCH EXISTING COATING AND FINISH.

- PAINTING APPLICATION:**
- INSPECT SURFACES. REPORT UNSATISFACTORY CONDITIONS IN WRITING; BEGINNING WORK MEANS ACCEPTANCE OF SUBSTRATE.
 - COMPLY WITH MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS FOR PREPARATION, PRIMING AND COATING WORK. COORDINATE WITH WORK OF OTHER SECTIONS.
 - MATCH APPROVED MOCK-UPS FOR COLOR, TEXTURE, AND PATTERN. RE-COAT OR REMOVE AND REPLACE WORK WHICH DOES NOT MATCH OR SHOWS LOSS OF ADHESION.
 - CLEAN UP, TOUCH UP AND PROTECT WORK.

- TOUCHUP PAINTING:**
- GALVANIZING DAMAGE AND ALL BOLTS AND NUTS SHALL BE TOUCHED UP AFTER TOWER ERECTION WITH "GALVANOK," "DRY GALV," OR "ZINC-IT"
 - FIELD TOUCHUP PAINT SHALL BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS.
 - ALL METAL COMPONENTS SHALL BE HANDLED WITH CARE TO PREVENT DAMAGE TO THE COMPONENTS, THEIR PRESERVATIVE TREATMENT, OR THEIR PROTECTIVE COATINGS.

SECTION 11 700 - ANTENNA ASSEMBLY, REMOTE RADIO HEADS AND CABLE INSTALLATION

SUMMARY:
THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRH'S, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

ANTENNAS AND RRH'S:
THE NUMBER AND TYPE OF ANTENNAS AND RRH'S TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

HYBRID CABLE:
HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS.

JUMPERS AND CONNECTORS:
FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRH'S AND ANTENNAS. JUMPERS SHALL BE TYPE LDF 4, FLC 12-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRH'S AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE. DO NOT USE SUPERFLEX OUTDOORS. JUMPERS SHALL BE FACTORY FABRICATED IN APPROPRIATE LENGTHS WITH A MAXIMUM OF 4 FEET EXCESS PER JUMPER AND HAVE CONNECTORS AT EACH END, MANUFACTURED BY SUPPLIER. IF JUMPERS ARE FIELD FABRICATED, FOLLOW MANUFACTURER'S REQUIREMENTS FOR INSTALLATION OF CONNECTORS

REMOTE ELECTRICAL TILT (RET) CABLES:

MISCELLANEOUS:
INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

ANTENNA INSTALLATION:
THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS.

- A. THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN 1 DEGREE.
- B. ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE DRAWINGS.

HYBRID CABLES INSTALLATION:

- A. THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
- B. THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS FOR BENDING RADI.
- C. EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION.
- FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE PERMANENTLY FASTENED TO THE COAX LADDER AT 4'-0" OC USING NON-MAGNETIC STAINLESS STEEL CLIPS.
 - FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE MMBTS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES:
 - FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH @ 18" OC. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.
 - DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY NELCO PRODUCTS OR EQUAL.

- FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL THE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.
- CABLE INSTALLATION:
 - INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION MANAGER.
 - CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES WILL BE PROPERLY ROUTED IN THE CABLE ENVELOP AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSLINGS.
 - HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURER'S RECOMMENDED MAXIMUM BEND RADIUS.
- GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED ON DRAWINGS.
- HYBRID CABLE COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED PER SPRINT TS-0200 CURRENT VERSION.
- HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1

WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND KITS:

- A. ALL FIBER & COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED.
- B. WEATHERPROOFING USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES.
- COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP OF 2" ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING. PROVIDE 3M COLD SHRINK CXS SERIES OR EQUAL.
 - SELF-AMALGAMATING TAPE: CLEAN SURFACES. APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE SELF-AMALGAMATING TAPE.
 - 3M SLIM LOCK CLOSURE 716; SUBSTITUTIONS WILL NOT BE ALLOWED.
 - OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE.

SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE STATIONS (MMBTS) AND RELATED EQUIPMENT

SUMMARY:
A. THIS SECTION SPECIFIES MMBTS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BUT NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFC).

- B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRE BY THE APPLICABLE INSTALLATION MOPS.

- C. COMPLY WITH MANUFACTURERS INSTALLATION AND START-UP REQUIREMENTS
- DC CIRCUIT BREAKER LABELING**

A. LABEL CIRCUIT BREAKERS ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1.

SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE TRANSCIEVER STATIONS (MMBTS) AND RELATED EQUIPMENT

SUMMARY:
A. THIS SECTION SPECIFIES MMBTS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BUT NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFC).

- B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRE BY THE APPLICABLE INSTALLATION MOPS.

- C. COMPLY WITH MANUFACTURERS INSTALLATION AND START-UP REQUIREMENTS
- SUPPORTING DEVICES:**

- A. MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING:
- ALLIED TUBE AND CONDUIT
 - B-LINE SYSTEM
 - UNISTRUT DIVERSIFIED PRODUCTS
 - THOMAS & BETTS
- B. FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS:
- EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
 - POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED SERVICE.
 - FASTEN BY MEANS OF WOOD SCREWS ON WOOD.
 - TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
 - CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY.
 - MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL.
 - EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED.
 - DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL STRUCTURES.
 - IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.

- SUPPORTING DEVICES:**
- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
- D. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
- E. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE SLABS.

ELECTRICAL IDENTIFICATION:

A. INSTALL AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.

B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT

- CONDUIT:**
- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR ENCASED RUNS IN CONCRETE. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXCEPT GALVANIZED. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS C80.1, FEDERAL SPECIFICATION WW-C-581 AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES. FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED EQUAL.
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP RADIUS ELBOWS.
- D. EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- E. LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6- FEET. LMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRE BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (21MM).

- HUBS AND BOXES:**
- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
- CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-2/GEDNEY OR EQUAL.
 - CABLE TERMINATORS FOR LMC SHALL BE ETCO - CL207S; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET. PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS, CROUSE-HINDS WAH SERIES OR EQUAL.
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKETED COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL.
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-2 GEDNEY, RACO, OR APPROVED EQUAL.

- SUPPLEMENTAL GROUNDING SYSTEM**
- A. FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM AS INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS AS INDICATED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

- EXISTING STRUCTURE:**
- A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

- CONDUIT AND CONDUCTOR INSTALLATION:**
- A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.



R.K. EXECUTIVE CENTRE
201 BOSTON POST ROAD WEST, SUITE 101
MAHAROUGH, MA 01752
(508) 481-7400
www.chappellengineering.com



THESE DOCUMENTS ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

CHECKED BY: JMT

APPROVED BY: JMT

| SUBMITTALS | | | |
|------------|----------|-------------------------|-----|
| REV. | DATE | DESCRIPTION | BY |
| | | | |
| | | | |
| 3 | 06/09/18 | ISSUED FOR CONST. FINAL | CMC |
| 2 | 01/10/18 | ISSUED FOR CONSTRUCTION | CMC |
| 1 | 10/25/17 | ISSUED FOR CONSTRUCTION | GBU |
| 0 | 09/20/17 | ISSUED FOR REVIEW | GBU |


SITE NUMBER:
BS23XC490

SITE NAME:
CEDAR ST. WATER TANK


SITE ADDRESS:
386 CEDAR STREET
ASHLAND, MA 01721

SHEET TITLE
OUTLINE SPECIFICATIONS


SHEET NUMBER
SP-3



COMPOUND PLAN
SCALE: 1" = 10' - 0"



EXISTING EQUIPMENT PLAN
SCALE: 3/8" = 1'-0"



PROPOSED EQUIPMENT PLAN
SCALE: 3/8" = 1'-0"

Sprint VISION
1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
(800) 357-7641

CENTERLINE
CENTERLINE COMMUNICATIONS
95 RYAN DRIVE, SUITE 1
RAYNHAM, MA 02767

CHAPPELL ENGINEERING ASSOCIATES, LLC
Civil-Structural-Land Surveying
R.K. EXECUTIVE CENTRE
201 BOSTON POST ROAD WEST, SUITE 101
MARLBOROUGH, MA 01752
(508) 481-7400
www.chappellengineering.com

COMMONWEALTH OF MASSACHUSETTS
DAVID A. CHAPPELL
CIVIL
No. 34706
REGISTERED PROFESSIONAL ENGINEER

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

CHECKED BY: JMT

APPROVED BY: JMT

SUBMITTALS

| REV. | DATE | DESCRIPTION | BY |
|------|----------|-------------------------|-----|
| 3 | 06/09/18 | ISSUED FOR CONST. FINAL | CMC |
| 2 | 01/10/18 | ISSUED FOR CONSTRUCTION | CMC |
| 1 | 10/24/17 | ISSUED FOR CONSTRUCTION | CMC |
| 0 | 09/20/17 | ISSUED FOR REVIEW | SDU |

SITE NUMBER:
BS23XC490
SITE NAME:
CEDAR ST. WATER TANK
SITE ADDRESS:
386 CEDAR STREET
ASHLAND, MA 01721

SHEET TITLE
COMPOUND & EQUIPMENT PLAN

SHEET NUMBER
A-1

SPECIAL CONSTRUCTION NOTE:

- SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
 - * COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY TOWER OWNER OR A&E VENDOR).
 - * COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).
 - * GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.

STRUCTURAL NOTE:


ADDITIONAL TOWER MAPPING AND STRUCTURAL ANALYSIS ARE REQUIRED PRIOR TO CONSTRUCTION. DRAWINGS ARE SUBJECT TO CHANGE PENDING OUTCOME OF STRUCTURAL ANALYSIS.

NOTES:


- ALL ANTENNAS AND ANCILLARY EQUIPMENT TO STAY WITHIN 10-FOOT LEASE ENVELOPE.
- ALL EQUIPMENT NOT TO OBSTRUCT CLIMBING LADDER OR SAFETY CLIMB.
- ALL ANTENNAS AND COAX ARE TO BE INSTALLED IN ACCORDANCE WITH THE STRUCTURAL ANALYSIS PROVIDED BY TOWER OWNER.

NOTE:

EXISTING AZIMUTHS FROM SPRINT SITE AUDIT, DATED 09.13.13.




NOTE: GROUND EQUIPMENT NOT SHOWN, FOR CLARITY.




ANTENNA STATUS LEGEND:

- EMPTY - EMPTY PIPE
- (E) - EXISTING
- (P) - INSTALL
- NV - SPRINT ANTENNA
- 2.5 - SPRINT ANTENNA



EXISTING ANTENNA PLAN
SCALE: N.T.S.



PROPOSED ANTENNA PLAN
SCALE: N.T.S.

SPECIAL INSTALLATION NOTE:
COAX JUMPERS FROM PROP. RRH TO PROP. ANTENNA SHALL NOT EXCEED 10'. NOTIFY SPRINT CM OF ANY DISCREPANCY.

NOTE: VERIFY PROPOSED AZIMUTHS WITH RF ENGINEER PRIOR TO INSTALLATION.



1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
(800) 357-7641



CENTERLINE COMMUNICATIONS
95 RYAN DRIVE, SUITE 1
RAYNHAM, MA 02767



R.K. EXECUTIVE CENTRE
201 BOSTON POST ROAD WEST, SUITE 101
MARLBOROUGH, MA 01752
(508) 481-7400
www.chappellengineering.com



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

CHECKED BY: JMT

APPROVED BY: JMT

SUBMITTALS

| REV. | DATE | DESCRIPTION | BY |
|------|----------|-------------------------|-----|
| 3 | 06/09/18 | ISSUED FOR CONST. FINAL | CM |
| 2 | 01/10/18 | ISSUED FOR CONSTRUCTION | CM |
| 1 | 10/21/17 | ISSUED FOR CONSTRUCTION | CM |
| 0 | 09/26/17 | ISSUED FOR REVIEW | SDU |

SITE NUMBER:
BS23XC490
SITE NAME:
CEDAR ST. WATER TANK
SITE ADDRESS:
396 CEDAR STREET
ASHLAND, MA 01721

SHEET TITLE
ELEVATION & ANTENNA PLANS

SHEET NUMBER
A-2

| | | | |
|--|--|----------------------------|----------------------------|
| Market: | Boston | | |
| Cascade ID | BS23XC490 | | |
| Augment Import Code: SPDM0U1_00_Macro_Upgrade | Augment: DO Macro Upgrade | | |
| Address: 396 Cedar Street, Ashland, MA, 01721 Latitude: 42.2533599 Longitude: -71.43963716 | Sprint Eng. Name: Bill Hastings Bill.Hastings@sprint.com Eng. Phone: 978-590-9700 Manager Name: Jonathan Hull Jonathan.Hull@sprint.com Manager Phone: 617-233-2920 RFE: Praveen Meesarapu Praveen.Meesarapu@sprint.com RFE Phone: 301-728-0006 | | |
| Detailed RFD5 Description: | Filter Analysis Complete: YES Border Analysis Complete: YES Channel Plan Complete: YES | | |
| Triband final config using NV + 800/2.5 dual band antenna. Adding 2nd 800 RRH and 2.5 RRH | | | |
| Site Data | Alpha | Beta | Gamma |
| 1900MHz_Azimuth | 10 | 170 | 270 |
| 1900MHz_No_of_Antennas | 1 | 1 | 1 |
| 1900MHz_RADCenter(ft) | 80.2 | 80.2 | 80.2 |
| 1900MHz_Antenna_Make | RRS | RRS | RRS |
| 1900MHz_Antenna_Model | APXVSP18-C-A20 | APXVSP18-C-A20 | APXVSP18-C-A20 |
| 1900MHz_Horizontal_Beamwidth | 65 | 65 | 65 |
| 1900MHz_Vertical_Beamwidth | 6 | 6 | 6 |
| 1900MHz_Antenna_Dimensions (ft) & Weight (lbs) | 72 x 11.8 x 7.9 28 (lbs) | 72 x 11.8 x 7.9 28 (lbs) | 72 x 11.8 x 7.9 28 (lbs) |
| 1900MHz_AntennaGain(dBd) | 18 | 18 | 18 |
| 1900MHz_E_Tilt | 0 | 0 | 0 |
| 1900MHz_M_Tilt | 0 | 0 | 0 |
| 1900_Effective_Tilt | 0 | 0 | 0 |
| 1900MHz_Carrier_Forecast_Year_2017 | | | |
| 1900MHz_RRH_Manufacturer | ALU | ALU | ALU |
| 1900MHz_RRH_Model | RRH 1900 4X45 65MHz | RRH 1900 4X45 65MHz | RRH 1900 4X45 65MHz |
| 1900MHz_RRH_Count | 1 | 1 | 1 |
| 1900MHz_RRH_Specs | 25 x 11.1 x 11.4 (60 lbs) | 25 x 11.1 x 11.4 (60 lbs) | 25 x 11.1 x 11.4 (60 lbs) |
| 1900MHz_RRH_Location | Top of the Pole/Tower | Top of the Pole/Tower | Top of the Pole/Tower |
| 1900MHz_Combiner_Model | No Combiner Required | No Combiner Required | No Combiner Required |
| 1900MHz_Power_Split_Ratio (Main/Split) | | | |
| 1900MHz_Splitter_Manufacturer | | | |
| 1900MHz_Splitter_Model | No Splitter Required | No Splitter Required | No Splitter Required |
| 1900MHz_Number_of_Splitters | 0 | 0 | 0 |
| 1900MHz_Top_Jumper #1_Length (RRH or Combiner-to-Antenna for TT or Main Coax to Antenna for Ground Mount, ft) | 8 | 8 | 8 |
| 1900MHz_Top_Jumper #1_Cable_Model (RRH or Combiner-to-Antenna for TT or Main Coax to Antenna for Ground Mount) | LCF12-50J | LCF12-50J | LCF12-50J |
| 1900MHz_Top_Jumper #2_Length (RRH to Combiner for TT if applicable, ft) | | | |
| 1900MHz_Top_Jumper #2_Cable_Model (RRH to Combiner for TT if applicable) | | | |
| 1900MHz_Main_Cable_Length (ft) | 105.2 | 105.2 | 105.2 |
| 1900MHz_Main_Cable_Model | Hyberflex Cable | Hyberflex Cable | Hyberflex Cable |
| 1900MHz_Bottom_Jumper #1_Length (Ground based RRH to Combiner-OR-Main Coax, ft) | | | |
| 1900MHz_Bottom_Jumper #1_Cable_Model (Ground based RRH to Combiner-OR-Main Coax) | | | |
| 1900MHz_Bottom_Jumper #2_Length (Ground based-Combiner to Main Coax, ft) | | | |
| 1900MHz_Bottom_Jumper #2_Cable_Model (Ground based-Combiner to Main Coax) | | | |

NOTES:
 1. COMMENTS IN RED TEXT PROVIDED BY A&E VENDOR.
 2. ANTENNA RAD CENTER BASED ON EQUIPMENT DATABASE AND STRUCTURAL ANALYSIS.
 3. SPRINT CM SHALL CONFIRM HYBRID CABLE LENGTH, COAX JUMPER LENGTH AND AISG CABLE LENGTH BEFORE PREPARING BOM. A&E RECOMMENDED HYBRID CABLE LENGTH BASED ON NV 2.5 EQUIPMENT AUDIT PLUS 20 FEET FOR (2) 10-FOOT COILS AT EACH END OF THE FIBER TRUNK.

NOTE:
 GENERAL CONTRACTOR/TOWER CREW SHALL VERIFY THAT THE LATEST RF DATA SHEET IS USED FOR EQUIPMENT INSTALLATION.

SPECIAL WORK NOTE:
 JUMPERS (COAX/AISG) FROM THE 2.5 RRH TO THE 2.5 ANTENNA CANNOT EXCEED 15'. NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY DISCREPANCY.

| | | | |
|--|--------------------------------------|--------------------------------------|--------------------------------------|
| 800MHz_RADCenter(ft) | 80.2 | 80.2 | 80.2 |
| 800MHz_AntennaMake | NA | NA | NA |
| 800MHz_AntennaModel | Antenna assigned on a different band | Antenna assigned on a different band | Antenna assigned on a different band |
| 800MHz_Horizontal_Beamwidth | NA | NA | NA |
| 800MHz_Vertical_Beamwidth | NA | NA | NA |
| 800MHz_Antenna_Dimensions (ft) & Weight (lbs) | NA NA | NA NA | NA NA |
| 800MHz_AntennaGain(dBd) | NA | NA | NA |
| 800MHz_E_Tilt | 0 | 0 | 0 |
| 800MHz_M_Tilt | 0 | 0 | 0 |
| 800 MHz_Effective Tilt (degrees) | 0 | 0 | 0 |
| 800MHz_RRH_Manufacturer | ALU | ALU | ALU |
| 800_Combiner_Model | No Combiner Required | No Combiner Required | No Combiner Required |
| 800MHz_RRH_Model | RRH 800 MHz 2x50W | RRH 800 MHz 2x50W | RRH 800 MHz 2x50W |
| 800MHz_RRH_Specs | 15.8 x 13 x 14 (64 lbs) | 15.8 x 13 x 14 (64 lbs) | 15.8 x 13 x 14 (64 lbs) |
| 800MHz_RRH_Count | 2 | 2 | 2 |
| 800MHz_RRH_Location | Top of the Pole/Tower | Top of the Pole/Tower | Top of the Pole/Tower |
| 800MHz_Power_Split_Ratio (Main/Split) | | | |
| 800MHz_Splitter_Manufacturer | | | |
| 800MHz_Splitter_Model | | | |
| 800MHz_Number_of_Splitters | 0 | 0 | 0 |
| 800_Top_Jumper #1_Length (RRH to Antenna for TT or Main Coax to Antenna for GM) | 8 | 8 | 8 |
| 800_Top_Jumper_Cable_Model (RRH to Antenna for TT or Main Coax to Antenna for GM) | LCF12-50J | LCF12-50J | LCF12-50J |
| 800MHz_Main_Coax_Cable_Length (ft) | NA | NA | NA |
| 800MHz_Main_Coax_Cable_Model | NA | NA | NA |
| 800_Bottom_Jumper #1_Length (Ground based RRH to Main Coax) | | | |
| 800_Bottom_Jumper #1_Cable_Model (Ground based RRH to Main Coax) | | | |
| 2500MHz_Azimuth | 10 | 170 | 270 |
| 2500MHz_No_of_Antennas | 1 | 1 | 1 |
| 2500MHz_RADCenter(ft) | 80.2 | 80.2 | 80.2 |
| 2500MHz_AntennaMake | Commscope | Commscope | Commscope |
| 2500MHz_AntennaModel | DT465B-2XR | DT465B-2XR | DT465B-2XR |
| 2500MHz_Horizontal_Beamwidth | 68 | 68 | 68 |
| 2500MHz_Vertical_Beamwidth | 4.3 | 4.3 | 4.3 |
| 2500MHz_AntennaHeight (ft) | 72 x 13.8 x 8.2 58 (lbs) | 72 x 13.8 x 8.2 58 (lbs) | 72 x 13.8 x 8.2 58 (lbs) |
| 2500MHz_AntennaGain(dBd) | 17.5 | 17.5 | 17.5 |
| 2500MHz_E_Tilt | 0 | -1 | 0 |
| 2500MHz_M_Tilt | 0 | 0 | 0 |
| 2500 MHz_Effective Tilt (degrees) | 0 | -1 | 0 |
| 2500MHz_RRH_Manufacturer | ALU | ALU | ALU |
| 2500_Combiner_Model | No Combiner Required | No Combiner Required | No Combiner Required |
| 2500MHz_RRH_Model | TD-RRH8x20-25 | TD-RRH8x20-25 | TD-RRH8x20-25 |
| 2500MHz_RRH_Count | 1 | 1 | 1 |
| 2500MHz_RRH_Location | Top of the Pole/Tower | Top of the Pole/Tower | Top of the Pole/Tower |
| 2500MHz_Power_Split_Ratio (Main/Split) | | | |
| 2500MHz_Splitter_Manufacturer | | | |
| 2500MHz_Splitter_Model | | | |
| 2500MHz_Number_of_Splitters | 0 | 0 | 0 |
| 2500_Top_Jumper #1_Length (RRH to Antenna for TT or Main Coax to Antenna for GM) | 8 | 8 | 8 |
| 2500_Top_Jumper_Cable_Model (RRH to Antenna for TT or Main Coax to Antenna for GM) | LCF12-50J | LCF12-50J | LCF12-50J |
| 2500MHz_Main_Cable_Length (ft) | 105.2 | | |
| 2500MHz_Main_Cable_Model | Hyberflex Cable | | |
| 2500_Bottom_Jumper #1_Length (Ground based RRH to Main Coax) | | | |
| 2500_Bottom_Jumper #1_Cable_Model (Ground based RRH to Main Coax) | | | |




1 INTERNATIONAL BLVD, SUITE 800
 MAHWAH, NJ 07495
 (800) 357-7641



CENTERLINE COMMUNICATIONS
 95 RYAN DRIVE, SUITE 1
 RAYNHAM, MA 02767



R.K. EXECUTIVE CENTRE
 201 BOSTON POST ROAD WEST, SUITE 101
 WAREHOUSING, MA 01752
 (508) 481-7400
www.chappellengineering.com



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

CHECKED BY: JMT

APPROVED BY: JMT

SUBMITTALS

| REV. | DATE | DESCRIPTION | BY |
|------|----------|-----------------------------|-----|
| 3 | 06/09/18 | ISSUED FOR CONST. FINAL | CMC |
| 2 | 01/10/18 | ISSUED FOR CONSTRUCTION CMC | |
| 1 | 10/20/17 | ISSUED FOR CONSTRUCTION | GM |
| 0 | 09/29/17 | ISSUED FOR REVIEW | GM |


SITE NUMBER:
 BS23XC490
 SITE NAME:
 CEDAR ST.
 WATER TANK
 SITE ADDRESS:
 396 CEDAR STREET
 ASHLAND, MA 01721

SHEET TITLE

RF DATA SHEET

SHEET NUMBER

A-3



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

CHECKED BY: JMT

APPROVED BY: JMT

| SUBMITTALS | | | |
|------------|----------|-------------------------|-----|
| REV. | DATE | DESCRIPTION | BY |
| 3 | 06/09/18 | ISSUED FOR CONST. FINAL | CMC |
| 2 | 01/10/18 | ISSUED FOR CONSTRUCTION | GMF |
| 1 | 10/21/17 | ISSUED FOR CONSTRUCTION | BDU |
| 0 | 09/20/17 | ISSUED FOR REVIEW | BDU |

SITE NUMBER:
BS23XC490


SITE NAME:
CEDAR ST. WATER TANK

SITE ADDRESS:
396 CEDAR STREET
ASHLAND, MA 01721


SHEET TITLE
RAN WIRING DIAGRAMS

SHEET NUMBER
A-4


- All RRH's at TOP with a direct jumper to the antenna port
- RED: 4 x 800
- BLUE: 4 x 1900
- YELLOW: 8 x 2500
- 4 Hybrid Cables Total (min)



PLUMBING DIAGRAM 1
SCALE: N.T.S. A-4



SPRINT 2.5 ALU SCENARIO 1 2
SCALE: N.T.S. A-4



CABLE COLOR-CODING SCHEMATIC 3
SCALE: N.T.S. A-4

SPRINT CONSTRUCTION STANDARDS:

GENERAL CONTRACTOR SHALL ADHERE TO THE FOLLOWING SPRINT CONSTRUCTION STANDARDS.

- CONSTRUCTION STANDARDS: INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES - (CURRENT VERSION), INCLUDING EXHIBITS A-M
- CONSTRUCTION SPECIFICATIONS: CONSTRUCTION STANDARDS EXHIBIT A - STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES (CURRENT VERSION).
- GROUNDING STANDARDS: EXTERIOR GROUNDING SYSTEM DESIGN, GROUNDING STANDARDS (SUPPLEMENT): ANTI-THEFT UPDATE TO SPRINT GROUNDING 082412 AND SPRINT ENGINEERING LETTER EL-0504 DATED 04.20.12.
- WEATHER PROOFING STANDARDS: EXCERPT FROM CONSTRUCTION STANDARDS EXHIBIT A, SECTION 3.6 WEATHERPROOFING CONNECTORS AND GROUND KITS.
- COLOR CODING: SPRINT NEXTEL ANT AND LINE COLOR CODING PER SPRINT TS-0200 CURRENT VERSION.
- GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND CL HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT IN RFDS, HALT ANTENNA WORK FOR WORK FOR ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO RF ENGINEER) USING SPRINT-PROVIDED CONTACT INFORMATION FOR FURTHER INSTRUCTIONS. IF SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE 2.5GHZ ANTENNA AT SAME CL AS 1.9GHZ ANTENNA AND EMAIL CORRECT CL HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER. UPDATE AS-BUILT DRAWING WITH CORRECT CL HEIGHT. ALSO EMAIL CORRECT 1900MHZ AND 800MHZ ANTENNA CL HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF ENGINEER.
- AISG TESTS TO VERIFY OPERATION IS TO BE PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED. VERIFY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT INCLUDING 800MHZ, 1.9GHZ, AND 2.5GHZ. TEST INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SWEEP TEST SPREADSHEET.
- GENERAL CONTRACTOR MUST INSURE THAT NO OBJECT IS LOCATED IN FRONT OF ANTENNA. THIS MEANS NO OBJECT IS TO BE LOCATED 45 DEGREES LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION. IN ADDITION, 2.5GHZ ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN 1 DEGREES. DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN 0.1 DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED, UPDATE AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER WITH AS-BUILTS SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL. [HTTP://WWW.3ZTELECOM.COM/ANTENNA-ALIGNMENT-TOOL/](http://www.3ztelecom.com/antenna-alignment-tool/).

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

CHECKED BY: JMT

APPROVED BY: JMT

| SUBMITTALS | | | |
|------------|----------|-------------------------|-----|
| REV. | DATE | DESCRIPTION | BY |
| 3 | 06/09/18 | ISSUED FOR CONST. FINAL | CJM |
| 2 | 01/10/18 | ISSUED FOR CONSTRUCTION | CJM |
| 1 | 10/21/17 | ISSUED FOR CONSTRUCTION | SDU |
| 0 | 09/29/17 | ISSUED FOR REVIEW | SDU |

SITE NUMBER:
BS23XC490
 SITE NAME:
CEDAR ST. WATER TANK
 SITE ADDRESS:
 396 CEDAR STREET
 ASHLAND, MA 01721

SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-5

| HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE | | | |
|--|------------------|--------|----------------|
| MANUF: | RFS | LENGTH | DC CONDUCTOR |
| CABLE | USE NV HYBRIFLEX | 5/8" | CABLE DIAMETER |
| HYBRIFLEX | <200' | 8 AWG | 1-1/4" |
| HYBRIFLEX | 225-300' | 6 AWG | 1-1/4" |
| HYBRIFLEX | 325-375' | 4 AWG | 1-1/4" |

RFS HYBRIFLEX RISER CABLE SCHEDULE

| Fiber Only (Existing DC Power) | Hybrid cable | Length |
|--------------------------------|---|--------|
| MN: HB05B-M12-050F | 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC | 50 ft |
| MN: HB05B-M12-075F | Connectors, 5/8" cable, 50 ft | 75 ft |
| MN: HB05B-M12-100F | | 100 ft |
| MN: HB05B-M12-125F | | 125 ft |
| MN: HB05B-M12-150F | | 150 ft |
| MN: HB05B-M12-175F | | 175 ft |
| MN: HB05B-M12-200F | | 200 ft |

| 8 AWG Power | Hybrid cable | Length |
|------------------------|---|--------|
| MN: HB114-08U3M12-050F | 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC | 50 ft |
| MN: HB114-08U3M12-075F | Connectors, 1 1/8" cable, 50 ft | 75 ft |
| MN: HB114-08U3M12-100F | | 100 ft |
| MN: HB114-08U3M12-125F | | 125 ft |
| MN: HB114-08U3M12-150F | | 150 ft |
| MN: HB114-08U3M12-175F | | 175 ft |
| MN: HB114-08U3M12-200F | | 200 ft |

| 6 AWG Power | Hybrid cable | Length |
|------------------------|--|--------|
| MN: HB114-13U3M12-225F | 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC | 225 ft |
| MN: HB114-13U3M12-250F | Connectors, 1 1/8" cable, 225 ft | 250 ft |
| MN: HB114-13U3M12-275F | | 275 ft |
| MN: HB114-13U3M12-300F | | 300 ft |

| 4 AWG Power | Hybrid cable | Length |
|------------------------|--|--------|
| MN: HB114-21U3M12-325F | 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC | 325 ft |
| MN: HB114-21U3M12-350F | Connectors, 1 1/8" cable, 325 ft | 350 ft |
| MN: HB114-21U3M12-375F | | 375 ft |

RFS HYBRIFLEX JUMPER CABLE SCHEDULE

| Fiber Only | Hybrid Jumper cable | Length |
|--------------------|---|--------|
| MN: HBF012-M3-5F1 | 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2" cable | 5 ft |
| MN: HBF012-M3-10F1 | 10 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2" cable | 10 ft |
| MN: HBF012-M3-15F1 | 15 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2" cable | 15 ft |
| MN: HBF012-M3-20F1 | 20 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2" cable | 20 ft |
| MN: HBF012-M3-25F1 | 25 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2" cable | 25 ft |
| MN: HBF012-M3-30F1 | 30 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2" cable | 30 ft |


| 8 AWG Power | Hybrid Jumper cable | Length |
|------------------------|--|--------|
| MN: HBF05B-08U1M3-5F1 | 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 3/8" cable | 5 ft |
| MN: HBF05B-08U1M3-10F1 | 10 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 3/8" cable | 10 ft |
| MN: HBF05B-08U1M3-15F1 | 15 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 3/8" cable | 15 ft |
| MN: HBF05B-08U1M3-20F1 | 20 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 3/8" cable | 20 ft |
| MN: HBF05B-08U1M3-25F1 | 25 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 3/8" cable | 25 ft |
| MN: HBF05B-08U1M3-30F1 | 30 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 3/8" cable | 30 ft |

| 6 AWG Power | Hybrid Jumper cable | Length |
|------------------------|--|--------|
| MN: HBF05B-13U1M3-5F1 | 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 3/8" cable | 5 ft |
| MN: HBF05B-13U1M3-10F1 | 10 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 3/8" cable | 10 ft |
| MN: HBF05B-13U1M3-15F1 | 15 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 3/8" cable | 15 ft |
| MN: HBF05B-13U1M3-20F1 | 20 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 3/8" cable | 20 ft |
| MN: HBF05B-13U1M3-25F1 | 25 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 3/8" cable | 25 ft |
| MN: HBF05B-13U1M3-30F1 | 30 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 3/8" cable | 30 ft |


| 4 AWG Power | Hybrid Jumper cable | Length |
|------------------------|--|--------|
| MN: HBF07B-21U1M3-5F1 | 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8" cable | 5 ft |
| MN: HBF07B-21U1M3-10F1 | 10 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8" cable | 10 ft |
| MN: HBF07B-21U1M3-15F1 | 15 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8" cable | 15 ft |
| MN: HBF07B-21U1M3-20F1 | 20 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8" cable | 20 ft |
| MN: HBF07B-21U1M3-25F1 | 25 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8" cable | 25 ft |
| MN: HBF07B-21U1M3-30F1 | 30 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8" cable | 30 ft |

* NOTE: SPRINT CM TO CONFIRM HYBRID RISER CABLE AND HYBRID JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.


2500MHz HYBRID CABLE X-SECTION & DATA
 SCALE: NTS




4 AWG



8 AWG & 6 AWG




FIBER ONLY




800 MHz RRH UNIT

RRH DETAILS

2500MHz RRH



2500MHz ANTENNA DETAILS



COMMSCOPE D1465B-2XR PANEL ANTENNA
 DIMENSIONS: 71.9"x13.8"x8.2"
 WEIGHT: 58.0 LBS W/ HARDWARE
 FREQUENCY RANGE: 817-869 MHz, 2490-2690 MHz

2500MHz ANTENNA DETAILS

3
 A-5



INSTALL NEW LTE BBU 2.5 GHz
 INSTALL NEW RECTIFIER SHELF
 & RECTIFIERS AS REQUIRED

SOURCE: SPRINT SITE AUDIT 09.13.13

EXISTING MM-BTS CABINET
 SCALE: NTS

1
 A-6




INSTALL (1) NEW BATTERY STRING
 IN EXIST. BBU CABINET

SOURCE: SPRINT SITE AUDIT 09.13.13

FRONT VIEW

EXISTING 2.5 POWER BBU CABINET
 SCALE: NTS

2
 A-6



FIBER JUNCTION BOX PENETRATION
 SCALE: NTS

3
 A-6

Sprint VISION
 1 INTERNATIONAL BLVD, SUITE 800
 MAHWAH, NJ 07495
 (800) 357-7641

CENTERLINE
 CENTERLINE COMMUNICATIONS
 95 RYAN DRIVE, SUITE 1
 RAYNHAM, MA 02767

CHAPPELL ENGINEERING ASSOCIATES, LLC
 Civil-Structural-Land Surveying
 R.K. EXECUTIVE CENTRE
 201 BOSTON POST ROAD WEST, SUITE 101
 MARLBOROUGH, MA 01752
 (508) 481-7400
 www.chappellengineering.com



THESE DOCUMENTS ARE
 CONFIDENTIAL AND ARE THE SOLE
 PROPERTY OF SPRINT AND MAY
 NOT BE REPRODUCED,
 DISSEMINATED OR REDISTRIBUTED
 WITHOUT THE EXPRESS WRITTEN
 CONSENT OF SPRINT.

CHECKED BY: JMT
 APPROVED BY: JMT


SUBMITTALS

| REV. | DATE | DESCRIPTION | BY |
|------|----------|-------------------------|-----|
| 3 | 06/09/18 | ISSUED FOR CONST. FINAL | CMC |
| 2 | 01/10/18 | ISSUED FOR CONSTRUCTION | CMC |
| 1 | 10/21/17 | ISSUED FOR CONSTRUCTION | EDU |
| 0 | 09/20/17 | ISSUED FOR REVIEW | EDU |


SITE NUMBER:
BS23XC490
 SITE NAME:
**CEDAR ST.
 WATER TANK**
 SITE ADDRESS:
 396 CEDAR STREET
 ASHLAND, MA 01721

SHEET TITLE
**EQUIPMENT
 DETAILS**

SHEET NUMBER
A-6



TYPICAL POWER & GROUNDING ONE-LINE
SCALE: NTS



SOURCE: SPRINT SITE AUDIT 09.13.13

EXIST. PPC BREAKER PANEL
SCALE: NTS

SPECIAL WORK NOTE:

- G.C. TO FURNISH AND INSTALL ALL COMPONENTS TO UPGRADE EXISTING ELECTRICAL SERVICE, CONDUIT, CONDUCTOR, PPC AND MCB IN ACCORDANCE WITH SPRINT CONSTRUCTION STANDARDS INV 2.5 ADDENDUM "ENGINEERING NOTICE 2013-02 (POWER UPGRADES) REV01" (OR CURRENT VERSION)
- G.C. TO FURNISH AND INSTALL UPGRADE THE EXISTING IMBTS BREAKER, CONDUCTOR, AND CONDUIT TO A MINIMUM NEC RATING FOR A 100-AMP, 240V CIRCUIT.
- FOR NEW OR REPAIRED GROUNDING EQUIPMENT, REFER TO SPRINT GROUNDING STANDARDS AND FOLLOWING (SUPPLEMENTS): -ANTI-THEFT UPDATE TO SPRINT GROUNDING DATED 08-24-12 (OR CURRENT VERSION) -SPRINT ENGINEERING LETTER EL-0504 DATED 04-20-12 (OR CURRENT VERSION)

ELECTRICAL NOTES

- ALL ELECTRICAL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE (NEC) AS WELL AS APPLICABLE STATE AND LOCAL CODES.
- THE ELECTRICAL CONTRACTOR SHALL COORDINATE ALL CONDUIT ROUTING WITH LOCAL UTILITY COMPANIES AND SPRINT CONSTRUCTION MANAGER.
- ALL CONDUITS ROUTED BELOW GRADE SHALL TRANSITION TO RIGID GALVANIZED ELBOWS WITH RIGID GALVANIZED STEEL CONDUIT ABOVE GRADE.
- ALL METAL CONDUITS SHALL BE PROVIDED WITH GROUNDING BUSHINGS.
- GENERAL CONTRACTOR SHALL PROVIDE ALL DIRECT BURIED CONDUITS WITH PLASTIC WARNING TAPE IDENTIFYING CONTENTS. TAPE COLORS SHALL BE ORANGE FOR TELEPHONE AND RED FOR ELECTRIC.
- ALL ELECTRICAL ITEMS SHALL BE U.L. APPROVED OR LISTED AND PROCURED PER SPECIFICATION REQUIREMENTS.
- THE ELECTRICAL WORK INCLUDES ALL LABOR AND MATERIALS DESCRIBED BY DRAWINGS AND SPECIFICATIONS INCLUDING INCIDENTAL WORK TO PROVIDE COMPLETE OPERATING AND APPROVED ELECTRICAL SYSTEM.
- GENERAL CONTRACTOR SHALL PAY FEES FOR PERMITS, AND IS RESPONSIBLE FOR OBTAINING SAID PERMITS AND COORDINATION OF INSPECTIONS.
- ELECTRICAL AND TELCO WIRING OUTSIDE A BUILDING AND EXPOSED TO WEATHER SHALL BE IN WATER TIGHT GALVANIZED RIGID STEEL CONDUITS OR SCHEDULE 80 PVC (AS PERMITTED BY CODE) AND WHERE REQUIRED IN LIQUID TIGHT FLEXIBLE METAL OR NONMETALLIC CONDUITS.
- BURIED CONDUIT SHALL BE SCHEDULE 40 PVC.
- ELECTRICAL WIRING SHALL BE COPPER WITH TYPE XHHW, THHN, OR THIN INSULATION.
- RUN ELECTRICAL CONDUIT OR CABLE BETWEEN ELECTRICAL UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE TELCO CABINET AND SBU CABINET AS INDICATED ON THIS DRAWING. PROVIDE FULL LENGTH PULL ROPE. COORDINATE INSTALLATION WITH UTILITY COMPANY.
- RUN TELCO CONDUIT OR CABLE BETWEEN TELEPHONE UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE TELCO CABINET AND SBU CABINET AS INDICATED ON THIS DRAWING. PROVIDE FULL LENGTH PULL ROPE IN INSTALLED TELCO CONDUIT. PROVIDE GREENLEED CONDUIT MEASURING TAPE AT EACH END.
- FIBER OPTIC CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 770-OPTICAL FIBER CABLES AND RACEWAYS.
- COMMUNICATIONS CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 800-COMMUNICATIONS SYSTEMS.

Sprint
VISION

1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
(800) 357-7641

CENTERLINE

CENTERLINE COMMUNICATIONS
95 RYAN DRIVE, SUITE 1
RAYNHAM, MA 02767

CHAPPELL ENGINEERING ASSOCIATES, LLC
Civil-Structural-Land Surveying

R.K. EXECUTIVE CENTRE
201 BOSTON POST ROAD WEST, SUITE 101
MARLBOROUGH, MA 01752
(508) 481-7400
www.chappellengineering.com

DAVID A. CHAPPELL
REGISTERED PROFESSIONAL ENGINEER
No. 34706

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

CHECKED BY: JMT
APPROVED BY: JMT

SUBMITTALS

| REV. | DATE | DESCRIPTION | BY |
|------|----------|-------------------------|-----|
| 3 | 05/09/18 | ISSUED FOR CONST. FINAL | CMC |
| 2 | 01/10/18 | ISSUED FOR CONSTRUCTION | CMC |
| 1 | 10/25/17 | ISSUED FOR CONSTRUCTION | SDU |
| 0 | 09/20/17 | ISSUED FOR REVIEW | SDU |


SITE NUMBER:
BS23XC490

SITE NAME:
CEDAR ST. WATER TANK

SITE ADDRESS:
386 CEDAR STREET
ASHLAND, MA 01721

SHEET TITLE
ONE-LINE DIAGRAM & PPC DETAILS

SHEET NUMBER
E-1



NOTE: HYBRIFLEX (FIBER & POWER) AND HYBRIFLEX (FIBER-ONLY) SHOWN. REFER TO RAN EQUIPMENT RFDs FOR SITE-SPECIFIC SCENARIO.

2.5 RAN EQUIPMENT GROUNDING SCHEMATIC
SCALE: N.T.S.

1
E-2

SYMBOL LEGEND


- EXOTHERMIC CONNECTION
- MECHANICAL CONNECTION
- CABLE GROUNDING KIT
- - - GROUNDING/BONDING
- CONDUIT

UNLESS NOTED OTHERWISE, ALL BONDING CONDUCTORS ARE #2 SOLID TINNED BOW.

NOTE: EXISTING NV EQUIPMENT CONDUITS NOT SHOWN FOR CLARITY. REFER TO RECORD AS-BUILT NV PHOTOS AND NV AS-BUILT DRAWINGS.

PROTECTIVE GROUNDING SYSTEMS GENERAL NOTES:

1. GROUNDING SHALL BE IN ACCORDANCE WITH NEC ARTICLE 250-GROUNDING AND BONDING.
2. GROUNDING SHALL BE IN ACCORDANCE WITH SPRINT SSED DOCUMENTS 3.018.02.004 "BONDING, GROUNDING AND TRANSIENT PROTECTION FOR CELL SITES" AND 3.018.10.002 "SITE RESISTANCE TO EARTH TESTING".
3. PROVIDE GROUND CONNECTIONS FOR ALL METALLIC STRUCTURES, ENCLOSURES, RACKS/STANDS AND OTHER CONDUCTIVE ITEMS ASSOCIATED WITH THE INSTALLATION OF CARRIER'S EQUIPMENT.
4. GROUND CONNECTIONS: CLEAN SURFACES THOROUGHLY BEFORE APPLYING GROUND LUGS OR CLAMPS. IF SURFACE IS COATED, REMOVE THE COATING, APPLY A NON-CORROSIVE APPROVED COMPOUND TO CLEAN SURFACE AND INSTALL LUGS OR CLAMPS. WHERE GALVANIZING IS REMOVED FROM METAL, IT SHALL BE PRIMED OR TOUCHED UP WITH "GALVAMOX" OR EQUAL.
5. ALL GROUNDING WIRES SHALL PROVIDE A STRAIGHT, DOWNWARD PATH TO GROUND WITH GRADUAL BENDS AS REQUIRED. GROUND WIRES SHALL NOT BE LOOPED OR SHARPLY BENT.
6. ALL CLAMPS AND SUPPORTS USED TO SUPPORT THE GROUNDING SYSTEM CONDUCTORS AND PVC CONDUITS SHALL BE PVC TYPE (NON CONDUCTIVE). DO NOT USE METAL BRACKETS OR SUPPORTS WHICH WOULD FORM A COMPLETE RING AROUND ANY GROUNDING CONDUCTOR.
7. ALL GROUND WIRES SHALL BE #2 SOLID TINNED BOW UNLESS NOTED OTHERWISE.
8. PROVIDE DEDICATED #2 AWG COPPER GROUND WIRE FROM EACH ANTENNA MOUNTING PIPE TO ASSOCIATED CIBIE.
9. GROUND ANTENNA BASES, FRAMES, CABLE RACKS, AND OTHER METALLIC COMPONENTS WITH #2 INSULATED TINNED STRANDED COPPER GROUNDING CONDUCTORS AND CONNECT TO INSULATED SURFACE MOUNTED GROUND BARS. CONNECTION DETAILS SHALL FOLLOW MANUFACTURER'S SPECIFICATIONS FOR GROUNDING.
10. EACH EQUIPMENT CABINET SHALL BE CONNECTED TO THE MASTER ISOLATION GROUND BAR (MGB) WITH #2 SOLID TINNED BOW EQUIPMENT CABINETS SHALL HAVE (2) CONNECTIONS.
11. GROUND HYBRIFLEX SHIELD AT TOP, BOTTOM AND AT TRANSITION TO HYBRIFLEX JUMPER CABLES AT EQUIPMENT CABINET ENTRANCE USING MANUFACTURER'S GUIDELINES. WHEN HYBRIFLEX CABLE EXCEEDS 200', GROUND AT INTERVALS NOT EXCEEDING 100'.
12. THE CONTRACTOR SHALL VERIFY THAT THE EXISTING GROUND BARS HAVE ENOUGH SPACE/HOLES FOR ADDITIONAL TWO HOLE LUGS.
13. EXOTHERMIC WELDING IS RECOMMENDED FOR GROUNDING CONNECTION WHERE PRACTICAL OTHERWISE. THE CONNECTION SHALL BE MADE USING COMPRESSION TYPE-2 HOLES, LONG BARREL LUGS OR DOUBLE CRIMP "C" CLAMP. THE COPPER CABLES SHALL BE COATED WITH AN ANTI-OXIDANT (THOMAS BETTS KORP-SHIELD) BEFORE MAKING THE CRIMP CONNECTIONS THE CONTRACTOR SHALL FOLLOW MANUFACTURER'S RECOMMENDED TORQUES ON THE BOLT ASSEMBLY TO SECURE CONNECTIONS.
14. AT ALL TERMINATIONS AT EQUIPMENT ENCLOSURES, PANEL AND FRAMES OF EQUIPMENT AND WHERE EXPOSED FOR GROUNDING, CONDUCTOR TERMINATION SHALL BE PERFORMED UTILIZING TWO HOLE BOLTED TONGUE COMPRESSION TYPE LUGS WITH STAINLESS STEEL SELF-TAPPING SCREWS.
15. THE MASTER GROUND BAR (MGB) SHALL BE MADE OF BARE 1/4"x2" COPPER (FOR OUTDOOR APPLICATIONS IT SHALL BE TINNED COPPER) AND LARGE ENOUGH TO ACCOMMODATE THE REQUIRED NUMBER OF GROUND CONNECTIONS. THE HARDWARE, SECURING THE MGB SHALL ELECTRICAL INSULATE THE MGB FROM ANY STRUCTURE TO WHICH IT IS FASTENED.
16. ALL BOLTS, WASHERS, AND NUTS USED ON GROUNDING CONNECTIONS SHALL BE STAINLESS STEEL.
17. ALL GROUNDING CONNECTIONS SHALL BE COATED WITH A COPPER SHIELD ANTI-CORROSIVE AGENT SUCH AS T&B KOPR SHIELD. VERIFY PRODUCT WITH SPRINT CONSTRUCTION MANAGER.
18. FOR NEW OR REPAIRED GROUNDING EQUIPMENT. REFER TO SPRINT GROUNDING STANDARDS AND FOLLOWING (SUPPLEMENTS):
-ANTI-THEFT UPDATE TO SPRINT GROUNDING DATED 08-24-12 (OR CURRENT VERSION)
-SPRINT ENGINEERING LETTER EL-0504 DATED 04-20-12 (OR CURRENT VERSION)




NOTES

1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR
SCALE: N.T.S.

2
E-2



TWO HOLE LUG
SCALE: N.T.S.

3
E-2



1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
(800) 357-7641



CENTERLINE COMMUNICATIONS
95 RYAN DRIVE, SUITE 1
RAYNHAM, MA 02767



R.K. EXECUTIVE CENTRE
201 BOSTON POST ROAD WEST, SUITE 101
MARLBOROUGH, MA 01752
(508) 481-7400
www.chappellengineering.com



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

CHECKED BY: JMT

APPROVED BY: JMT

SUBMITTALS

| REV. | DATE | DESCRIPTION | BY |
|------|----------|-------------------------|-----|
| 3 | 06/09/18 | ISSUED FOR CONST. FINAL | CM |
| 2 | 01/10/18 | ISSUED FOR CONSTRUCTION | CM |
| 1 | 10/21/17 | ISSUED FOR CONSTRUCTION | SDU |
| 0 | 09/29/17 | ISSUED FOR REVIEW | SDU |

SITE NUMBER:
BS23XC490
SITE NAME:
CEDAR ST.
WATER TANK
SITE ADDRESS:
396 CEDAR STREET
ASHLAND, MA 01721

SHEET TITLE
GROUNDING DETAILS
& NOTES

SHEET NUMBER

E-2

Appendix C– Mount Analysis

| | | |
|---|----------------|----------------------------------|
| tnxTower Chappell Engineering Assoc, LLC 201 Boston Post Road West Marlborough, MA 01752 Phone: (508) 481-7400 FAX: (508) 481-7406 | Job | Page 1 of 4 |
| | Project | Date 09:30:49 05/11/18 |
| | Client | Designed by CJS |

Tower Input Data

This tower is designed using the TIA-222-G standard.

The following design criteria apply:

Tower is located in Middlesex County, Massachusetts.

Basic wind speed of 105 mph.

Structure Class II.

Exposure Category B.

Topographic Category 1.

Crest Height 0.00 ft.

Nominal ice thickness of 1.0000 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 40 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 60 mph.

Connections use galvanized A325 bolts, nuts and locking devices. Installation per TIA/EIA-222 and AISC Specifications..

Tower members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards..

Welds are fabricated with ER-70S-6 electrodes..

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in pole design is 1.

Local bending stresses due to climbing loads, feedline supports, and appurtenance mounts are not considered.

Discrete Tower Loads

| Description | Face or Leg | Offset Type | Offsets: | | Azimuth Adjustment | Placement | C _A A _A Front | C _A A _A Side | Weight | |
|--------------------------|-------------------|----------------|-----------------------|------------|-----------------------|-----------|--|---------------------------------------|--------|-------|
| | | | Horz Lateral ft | Vert ft | | | | | | |
| Commscope DT465B-2XR | A | None | | | 0.0000 | 80.00 | No Ice | 9.66 | 5.98 | 0.060 |
| | | | | | | | 1/2" Ice | 10.22 | 6.44 | 0.118 |
| | | | | | | | 1" Ice | 10.79 | 6.91 | 0.182 |
| ALU 1900 RRH | A | None | | | 0.0000 | 80.00 | No Ice | 2.92 | 2.92 | 0.090 |
| | | | | | | | 1/2" Ice | 3.16 | 3.16 | 0.116 |
| | | | | | | | 1" Ice | 3.41 | 3.41 | 0.145 |
| ALU 800 RRH | A | None | | | 0.0000 | 80.00 | No Ice | 2.53 | 2.14 | 0.055 |
| | | | | | | | 1/2" Ice | 2.75 | 2.34 | 0.077 |
| | | | | | | | 1" Ice | 2.97 | 2.56 | 0.101 |
| ALU TD-RRH8x20-25 | A | None | | | 0.0000 | 80.00 | No Ice | 4.72 | 1.70 | 0.070 |
| | | | | | | | 1/2" Ice | 5.01 | 1.92 | 0.097 |
| | | | | | | | 1" Ice | 5.32 | 2.14 | 0.128 |
| AM-X-CD-15-85-00T w/pipe | A | None | | | 0.0000 | 0.00 | No Ice | 8.26 | 6.13 | 0.072 |
| | | | | | | | 1/2" Ice | 8.81 | 7.07 | 0.132 |
| | | | | | | | 1" Ice | 9.36 | 7.90 | 0.204 |
| Ericsson RRUS-12 | A | None | | | 0.0000 | 0.00 | No Ice | 3.67 | 1.35 | 0.058 |
| | | | | | | | 1/2" Ice | 3.93 | 1.52 | 0.081 |
| | | | | | | | 1" Ice | 4.19 | 1.70 | 0.108 |

| | | |
|---|----------------|----------------------------------|
| tnxTower Chappell Engineering Assoc, LLC 201 Boston Post Road West Marlborough, MA 01752 Phone: (508) 481-7400 FAX: (508) 481-7406 | Job | Page 2 of 4 |
| | Project | Date 09:30:49 05/11/18 |
| | Client | Designed by CJS |

Discrete Appurtenance Pressures - No Ice $G_H = 1.100$

| Description | Aiming Azimuth ° | Weight K | Offset _x ft | Offset _z ft | z ft | K _z | q _z psf | C _{AAc} Front ft ² | C _{AAc} Side ft ² |
|--------------------------|---------------------|--------------|---------------------------|---------------------------|---------|----------------|-----------------------|--|---|
| Commscope DT465B-2XR | 0.0000 | 0.060 | 0.00 | 0.00 | 80.00 | 0.927 | 25 | 9.66 | 5.98 |
| ALU 1900 RRH | 0.0000 | 0.090 | 0.00 | 0.00 | 80.00 | 0.927 | 25 | 2.92 | 2.92 |
| ALU 800 RRH | 0.0000 | 0.055 | 0.00 | 0.00 | 80.00 | 0.927 | 25 | 2.53 | 2.14 |
| ALU TD-RRH8x20-25 | 0.0000 | 0.070 | 0.00 | 0.00 | 80.00 | 0.927 | 25 | 4.72 | 1.70 |
| AM-X-CD-15-85-00T w/pipe | 0.0000 | 0.072 | 0.00 | 0.00 | 0.00 | 1.000 | 27 | 8.26 | 6.13 |
| Ericsson RRUS-12 | 0.0000 | 0.058 | 0.00 | 0.00 | 0.00 | 1.000 | 27 | 3.67 | 1.35 |
| Sum Weight: | | 0.405 | | | | | | | |

Discrete Appurtenance Vectors - No Ice

| <i>Commscope DT465B-2XR - Elevation 80 - None A</i> | | | | | | | |
|--|---------------------|---------------------|---------------------|---------------------|----------------------------|----------------------------|------------------|
| Wind Azimuth ° | F _a K | F _s K | V _x K | V _z K | OTM _x kip-ft | OTM _z kip-ft | Torque kip-ft |
| 0 | 0.264 | 0.000 | 0.000 | -0.264 | -21.13 | 0.00 | 0.00 |
| 90 | 0.264 | 0.000 | 0.264 | 0.000 | 0.00 | -21.13 | 0.00 |
| 180 | 0.264 | 0.000 | 0.000 | 0.264 | 21.13 | 0.00 | 0.00 |
| <i>ALU 1900 RRH - Elevation 80 - None A</i> | | | | | | | |
| Wind Azimuth ° | F _a K | F _s K | V _x K | V _z K | OTM _x kip-ft | OTM _z kip-ft | Torque kip-ft |
| 0 | 0.080 | 0.000 | 0.000 | -0.080 | -6.38 | 0.00 | 0.00 |
| 90 | 0.080 | 0.000 | 0.080 | 0.000 | 0.00 | -6.38 | 0.00 |
| 180 | 0.080 | 0.000 | 0.000 | 0.080 | 6.38 | 0.00 | 0.00 |
| <i>ALU 800 RRH - Elevation 80 - None A</i> | | | | | | | |
| Wind Azimuth ° | F _a K | F _s K | V _x K | V _z K | OTM _x kip-ft | OTM _z kip-ft | Torque kip-ft |
| 0 | 0.069 | 0.000 | 0.000 | -0.069 | -5.53 | 0.00 | 0.00 |
| 90 | 0.069 | 0.000 | 0.069 | 0.000 | 0.00 | -5.53 | 0.00 |
| 180 | 0.069 | 0.000 | 0.000 | 0.069 | 5.53 | 0.00 | 0.00 |
| <i>ALU TD-RRH8x20-25 - Elevation 80 - None A</i> | | | | | | | |
| Wind Azimuth ° | F _a K | F _s K | V _x K | V _z K | OTM _x kip-ft | OTM _z kip-ft | Torque kip-ft |
| 0 | 0.129 | 0.000 | 0.000 | -0.129 | -10.33 | 0.00 | 0.00 |
| 90 | 0.129 | 0.000 | 0.129 | 0.000 | 0.00 | -10.33 | 0.00 |
| 180 | 0.129 | 0.000 | 0.000 | 0.129 | 10.33 | 0.00 | 0.00 |
| <i>AM-X-CD-15-85-00T w/pipe - Elevation 0 - None A</i> | | | | | | | |
| Wind Azimuth ° | F _a K | F _s K | V _x K | V _z K | OTM _x kip-ft | OTM _z kip-ft | Torque kip-ft |
| 0 | 0.244 | 0.000 | 0.000 | -0.244 | 0.00 | 0.00 | 0.00 |
| 90 | 0.244 | 0.000 | 0.244 | 0.000 | 0.00 | 0.00 | 0.00 |
| 180 | 0.244 | 0.000 | 0.000 | 0.244 | 0.00 | 0.00 | 0.00 |
| <i>Ericsson RRUS-12 - Elevation 0 - None A</i> | | | | | | | |
| Wind Azimuth ° | F _a K | F _s K | V _x K | V _z K | OTM _x kip-ft | OTM _z kip-ft | Torque kip-ft |
| 0 | 0.108 | 0.000 | 0.000 | -0.108 | 0.00 | 0.00 | 0.00 |
| 90 | 0.108 | 0.000 | 0.108 | 0.000 | 0.00 | 0.00 | 0.00 |
| 180 | 0.108 | 0.000 | 0.000 | 0.108 | 0.00 | 0.00 | 0.00 |

| | | |
|---|----------------|----------------------------------|
| tnxTower Chappell Engineering Assoc, LLC 201 Boston Post Road West Marlborough, MA 01752 Phone: (508) 481-7400 FAX: (508) 481-7406 | Job | Page 3 of 4 |
| | Project | Date 09:30:49 05/11/18 |
| | Client | Designed by CJS |

Discrete Appurtenance Pressures - With Ice $G_H = 1.100$

| Description | Aiming Azimuth ° | Weight K | Offset _x ft | Offset _z ft | z ft | K _z | q _z psf | C _{AAc} Front ft ² | C _{AAc} Side ft ² | t _z in |
|----------------------------|---------------------|-------------|---------------------------|---------------------------|---------|----------------|-----------------------|---|--|----------------------|
| Commscope DT465B-2XR | 0.0000 | 0.366 | 0.00 | 0.00 | 80.00 | 0.927 | 4 | 12.18 | 8.10 | 2.1852 |
| ALU 1900 RRH | 0.0000 | 0.231 | 0.00 | 0.00 | 80.00 | 0.927 | 4 | 4.05 | 4.05 | 2.1852 |
| ALU 800 RRH | 0.0000 | 0.176 | 0.00 | 0.00 | 80.00 | 0.927 | 4 | 3.55 | 3.11 | 2.1852 |
| ALU TD-RRH8x20-25 | 0.0000 | 0.219 | 0.00 | 0.00 | 80.00 | 0.927 | 4 | 6.07 | 2.72 | 2.1852 |
| AM-X-CD-15-85-00T | 0.0000 | 0.072 | 0.00 | 0.00 | 0.00 | 1.000 | 4 | 8.26 | 6.13 | 0.0000 |
| w/pipe Ericsson RRUS-12 | 0.0000 | 0.058 | 0.00 | 0.00 | 0.00 | 1.000 | 4 | 3.67 | 1.35 | 0.0000 |
| Sum Weight: | | 1.122 | | | | | | | | |

Discrete Appurtenance Vectors - With Ice

| <i>Commscope DT465B-2XR - Elevation 80 - None A</i> | | | | | | | |
|--|---------------------|---------------------|---------------------|---------------------|----------------------------|----------------------------|------------------|
| Wind Azimuth ° | F _a K | F _s K | V _x K | V _z K | OTM _x kip-ft | OTM _z kip-ft | Torque kip-ft |
| 0 | 0.048 | 0.000 | 0.000 | -0.048 | -3.87 | 0.00 | 0.00 |
| 90 | 0.048 | 0.000 | 0.048 | 0.000 | 0.00 | -3.87 | 0.00 |
| 180 | 0.048 | 0.000 | 0.000 | 0.048 | 3.87 | 0.00 | 0.00 |
| <i>ALU 1900 RRH - Elevation 80 - None A</i> | | | | | | | |
| Wind Azimuth ° | F _a K | F _s K | V _x K | V _z K | OTM _x kip-ft | OTM _z kip-ft | Torque kip-ft |
| 0 | 0.016 | 0.000 | 0.000 | -0.016 | -1.29 | 0.00 | 0.00 |
| 90 | 0.016 | 0.000 | 0.016 | 0.000 | 0.00 | -1.29 | 0.00 |
| 180 | 0.016 | 0.000 | 0.000 | 0.016 | 1.29 | 0.00 | 0.00 |
| <i>ALU 800 RRH - Elevation 80 - None A</i> | | | | | | | |
| Wind Azimuth ° | F _a K | F _s K | V _x K | V _z K | OTM _x kip-ft | OTM _z kip-ft | Torque kip-ft |
| 0 | 0.014 | 0.000 | 0.000 | -0.014 | -1.13 | 0.00 | 0.00 |
| 90 | 0.014 | 0.000 | 0.014 | 0.000 | 0.00 | -1.13 | 0.00 |
| 180 | 0.014 | 0.000 | 0.000 | 0.014 | 1.13 | 0.00 | 0.00 |
| <i>ALU TD-RRH8x20-25 - Elevation 80 - None A</i> | | | | | | | |
| Wind Azimuth ° | F _a K | F _s K | V _x K | V _z K | OTM _x kip-ft | OTM _z kip-ft | Torque kip-ft |
| 0 | 0.024 | 0.000 | 0.000 | -0.024 | -1.93 | 0.00 | 0.00 |
| 90 | 0.024 | 0.000 | 0.024 | 0.000 | 0.00 | -1.93 | 0.00 |
| 180 | 0.024 | 0.000 | 0.000 | 0.024 | 1.93 | 0.00 | 0.00 |
| <i>AM-X-CD-15-85-00T w/pipe - Elevation 0 - None A</i> | | | | | | | |
| Wind Azimuth ° | F _a K | F _s K | V _x K | V _z K | OTM _x kip-ft | OTM _z kip-ft | Torque kip-ft |
| 0 | 0.035 | 0.000 | 0.000 | -0.035 | 0.00 | 0.00 | 0.00 |
| 90 | 0.035 | 0.000 | 0.035 | 0.000 | 0.00 | 0.00 | 0.00 |
| 180 | 0.035 | 0.000 | 0.000 | 0.035 | 0.00 | 0.00 | 0.00 |
| <i>Ericsson RRUS-12 - Elevation 0 - None A</i> | | | | | | | |
| Wind Azimuth ° | F _a K | F _s K | V _x K | V _z K | OTM _x kip-ft | OTM _z kip-ft | Torque kip-ft |
| 0 | 0.016 | 0.000 | 0.000 | -0.016 | 0.00 | 0.00 | 0.00 |
| 90 | 0.016 | 0.000 | 0.016 | 0.000 | 0.00 | 0.00 | 0.00 |
| 180 | 0.016 | 0.000 | 0.000 | 0.016 | 0.00 | 0.00 | 0.00 |

tnxTower

**Chappell Engineering Assoc,
LLC**

201 Boston Post Road West
Marlborough, MA 01752
Phone: (508) 481-7400
FAX: (508) 481-7406

Job

Page

4 of 4

Project


Date

09:30:49 05/11/18


Client


Designed by

CJS




DATE: 5/14/18





SCALE = 1:22

DATE: 5/14/18



Cedar St WT Ashland MA

*Prepared by:**Date:* 5/14/18**Load no. 1: Front No Ice (units - kips ft.)**

/ JOINT LOADS

FX1 0.13 FX3 -0.03 N 15 13

FX1 0.12 FX3 -0.06 N 11 9

FX1 0.13 FX3 -0.09 N 14 12 10

/ END

FORCE SUMMATION

FX1=0.89 kip

FX2=0. kip

FX3=-0.45 kip

Load no. 2: Side No Ice (units - kips ft.)

/ JOINT LOADS

/ JOINT LOADS

FX2 0.13 FX3 -0.03 N 15 13

FX2 0.12 FX3 -0.06 N 11 9

FX2 0.13 FX3 -0.09 N 14 12 10

/ END

FORCE SUMMATION

FX1=0. kip

FX2=0.89 kip

FX3=-0.45 kip

Load no. 3: Front Ice (units - kips ft.)

/ JOINT LOADS

/ JOINT LOADS

FX1 0.02 FX3 -0.09 N 15 13

FX1 0.018 FX3 -0.102 N 11 9

FX1 0.02 FX3 -0.108 N 14 12 10

/ END

FORCE SUMMATION

FX1=0.136 kip

FX2=0. kip

FX3=-0.708 kip

Cedar St WT Ashland MA

Prepared by:

Date: 5/14/18

Load no. 4: Side Ice (units - kips ft.)

/ JOINT LOADS
 / JOINT LOADS
 / JOINT LOADS
 FX2 0.02 FX3 -0.09 N 15 13
 FX2 0.018 FX3 -0.102 N 11 9
 FX2 0.02 FX3 -0.108 N 14 12 10
 / END

FORCE SUMMATION

FX1=0. kip
 FX2=0.136 kip
 FX3=-0.708 kip

Load no. 5: Selfweight (units - kips ft.)

/ BEAM LOADS
 SELF X3 -1. B 1 TO 15
 / END

FORCE SUMMATION

FX1=0. kip
 FX2=0. kip
 FX3=-0.1814 kip

Load no. 6: Front Frame Ice (units - kips ft.)

/ BEAM LOADS
 DIST GL FX1 0.0015 B 15 14 13 12 11 10 9 8 7 6 5 3 4
 / END

FORCE SUMMATION

FX1=0.0348 kip
 FX2=0. kip
 FX3=0. kip

Load no. 7: Side Frame Ice (units - kips ft.)

/ BEAM LOADS
 / BEAM LOADS
 DIST GL FX2 0.0015 B 15 14 13 12 11 10 9 8 7 6 5 3 4
 / END

Cedar St WT Ashland MA

*Prepared by:**Date:* 5/14/18**Load no. 7: Side Frame Ice (units - kips ft.)****FORCE SUMMATION**

FX1=0. kip
FX2=0.0348 kip
FX3=0. kip

Load no. 8: Front Frame No Ice (units - kips ft.)

/ BEAM LOADS
/ BEAM LOADS
DIST GL FX1 0.008 B 15 14 13 12 11 10 9 8 7 6 5 3 4
/ END

FORCE SUMMATION


FX1=0.1854 kip
FX2=0. kip
FX3=0. kip

Load no. 9: Side Frame No Ice (units - kips ft.)

/ BEAM LOADS
/ BEAM LOADS
/ BEAM LOADS
DIST GL FX2 0.008 B 15 14 13 12 11 10 9 8 7 6 5 3 4
/ END STATIC

FORCE SUMMATION


FX1=0. kip
FX2=0.1854 kip
FX3=0. kip




SCALE = 1:25

UNITS: kip ft

DATE: 5/14/18







SCALE = 1:25

UNITS: kip ft

DATE: 5/14/18







SCALE = 1:25

UNITS: kip ft

DATE: 5/14/18







SCALE = 1:25

UNITS: kip ft

DATE: 5/14/18




Load 5: Selfweight




SCALE = 1:25

UNITS: kip ft

DATE: 5/14/18




Load 6: Front Frame Ice




SCALE = 1:25

UNITS: kip ft

DATE: 5/14/18







SCALE = 1:25

UNITS: kip ft

DATE: 5/14/18




Load 8: Front Frame No Ice




SCALE = 1:25

UNITS: kip ft

DATE: 5/14/18






SCALE = 1:25

UNITS: kip ft


DATE: 5/14/18



Cedar St WT Ashland MA

*Prepared by:**Date:* 5/14/18**COMBINATIONS TABLE***Comb.*


| | |
|---|--|
| 1 | Front No Ice 1 * 1.00 + 5 * 1.20 + 8 * 1.00 |
| 2 | Side No Ice 2 * 1.00 + 5 * 1.20 + 9 * 1.00 |
| 3 | Front Iced 3 * 1.00 + 5 * 1.40 + 6 * 1.00 |
| 4 | Side Iced 4 * 1.00 + 5 * 1.40 + 7 * 1.00 |



SCALE = 1:24


UNITS: kip*ft

DATE: 5/14/18



M2 MOMENT


LOADS ENVELOPE



SCALE = 1:24


UNITS: kip*ft

DATE: 5/14/18



M3 MOMENT


LOADS ENVELOPE



SCALE = 1:24


UNITS: kip

DATE: 5/14/18



X1 REACTIONS


LOADS ENVELOPE



SCALE = 1:24


UNITS: kip

DATE: 5/14/18



X2 REACTIONS


LOADS ENVELOPE



SCALE = 1:24

UNITS: kip

DATE: 5/14/18



X3 REACTIONS

LOADS ENVELOPE

Cedar St WT Ashland MA

Code: AISC-LRFD

Prepared by:

Date: 5/14/18

Results Summary Table

| Beam | Section | Com | Defl L/ | Slen | CAPACITY | | | | | Combined Axial+Mom |
|------|-----------|-----|------------|------|----------|-----|-------|------|------|-----------------------|
| | | | | | Axial | Dir | Shear | Mom | LTB | |
| 3 | L 3x3x1/4 | 2 | 9999 | 82 | -0.02 | MJ | 0.00 | 0.01 | 0.01 | 0.02 |
| | | | | | | MI | 0.00 | 0.01 | 0.00 | |
| 4 | L 3x3x1/4 | 2 | 9999 | 82 | -0.03 | MJ | 0.00 | 0.01 | 0.01 | 0.03 |
| | | | | | | MI | 0.00 | 0.01 | 0.00 | |
| 15 | PIPE 3 | 2 | 823 | 121 | -0.02 | MJ | 0.03 | 0.19 | 0.19 | 0.20 |
| | | | | | | MI | 0.02 | 0.19 | 0.00 | |

Cedar St WT Ashland MA


Code: AISC-LRFD

Prepared by:

Date: 5/14/18

Detailed Results Table for Beam 15 - 5

Moments: kips*foot , Forces: kips , Stresses: ksi , Section prop.: inch



CONSTRAINTS

- Sections : Check
- Steel Grade: A53

DESIGN DATA


- Kx = 1.00 - Ky = 1.00
- Allow. Slend. : 200 (compr.) 300 (tens.)
- Allowable Deflection : 1/240
- Tension Area Reduction Factor : 1.00
- Building type : Unbraced

Section: PIPE 3

Ix = 3.02 Iy = 3.02in4 Zx = 2.33 Zy = 2.33in3 Area = 2.23
D = 3.50 t = 0.22in
J = 6.03 Cw = 0.00in6


DESIGN COMBINATION = 2

M2 Moment Diagram



Max. AXIAL Force = 0.01 (tens.), -0.42 (compr.) Max. SHEAR Force = 0.01

M3 Moment Diagram



Max. AXIAL Force = 0.01 (tens.), -0.42 (compr.) Max. SHEAR Force = 0.52

SECTION CLASSIFICATION: *** COMPACT ***

Limiting Ratios: Compact Non-Compact Slender -axial
d/t= 16.16 < 58.0 256.9 91.1 (Fy= 35.0 R = 0.005)

| DESIGN | EQUATION | FACTORS | VALUES | RESULT |
|------------------------------------|--|--------------|-------------------------------|--------|
| V2 Shear G2.1.b-i | $V_u/0.9V_n < 1.00$ $V_n = 0.6 \cdot F_y \cdot A_w$ | $A_w = 1.11$ | $V_u = 0.52$ $V_n = 23.43$ | 0.02 |
| M3 Moment (F8-1) without LTB | $\frac{M}{0.9M_n} < 1.00$ | $Z = 2.33$ | $M = 1.17$ $M_n = 6.81$ | 0.19 |
| M2 Moment (F8-1) without LTB | $\frac{M}{0.9M_n} < 1.00$ | $Z = 2.33$ | $M = 0.02$ $M_n = 6.81$ | 0.00 |

Cedar St WT Ashland MA

Code: AISC-LRFD

Prepared by:

Date: 5/14/18


Detailed Results Table for Beam 15 - 5

Moments: kips*foot , Forces: kips , Stresses: ksi , Section prop.: inch

| DESIGN | EQUATION | FACTORS | VALUES | RESULT |
|-------------------------------------|--|--|--|--------|
| Deflection | $\frac{\text{defl.}}{L / 240} < 1.00$ | | defl = 0.21982 | 0.29 |
| Axial Force (E3-1) | $\frac{P_u}{0.9A_g F_{cr}} < 1.00$ Slender. reduct. | (kL/r) _x = 113 (kL/r) _y = 113 x = 0.73 | P _u = 0.42 A _g = 2.23 F _{cr} = 18.25 y = 0.73 | 0.01 |
| Combined Forces (compress.) (H1-1b) | $\frac{P_r}{2\phi P_n} + \frac{M_{rx}}{\phi M_{nx}} + \frac{M_{ry}}{\phi M_{ny}} < 1.00$ | C _{mx} = 1.00 C _{my} = 1.00 P _{ex} = 50.19 P _{ey} = 50.19 | M _{rx} = 0.02 M _{ry} = 1.18 B _{1x} = 1.01 B _{1y} = 1.01 | 0.20 |

Detailed Results Table for Beam 4

Moments: kips*foot , Forces: kips , Stresses: ksi , Section prop.: inch



CONSTRAINTS

- Sections : Check
- Steel Grade: A36

DESIGN DATA


- K_x = 1.00 - K_y = 1.00
- Allow. Slend. : 200 (compr.) 300 (tens.)
- Allowable Deflection : 1/240
- Tension Area Reduction Factor : 1.00
- Building type : Unbraced

Section: L 3x3x1/4

I_x = 1.24 I_y = 1.24in⁴ S_x = 0.58 S_y = 0.58in³ Area = 1.44
h = 3.00 b = 3.00in t = 0.25 e_y = 2.15in e_x = 2.15in
J = 0.03 C_w = 0.00in⁶ I_v = 0.50 in⁴

DESIGN COMBINATION = 2

M2 Moment Diagram



Max. AXIAL Force = -1.02 (compr.) Max. SHEAR Force = 0.01

Cedar St WT Ashland MA


Code: AISC-LRFD

Prepared by:

Date: 5/14/18

Detailed Results Table for Beam 4

Moments: kips*foot , Forces: kips , Stresses: ksi , Section prop.: inch



Max. AXIAL Force = -1.02 (compr.) Max. SHEAR Force = 0.01


SECTION CLASSIFICATION: *** COMPACT ***

Limiting Ratios: Compact Non-Compact Slender -axial
 d/t= 12.10 < 15.3 25.8 12.8 (Fy= 36.0)
 b/t= 12.10 < 15.3 25.8 12.8

| DESIGN | EQUATION | FACTORS | VALUES | RESULT |
|--------------------------------------|--|---|--|--------|
| M3 Moment (F10-1) without LTB | $\frac{M}{0.9M_n} < 1.00$ | Z = 0.58 | M = 0.01 Mn = 2.60 | 0.01 |
| M2 Moment (F10-1) without LTB | $\frac{M}{0.9M_n} < 1.00$ | Z = 0.58 | M = 0.01 Mn = 2.60 | 0.01 |
| Axial Force (E3-1) | $\frac{P_u}{0.9A_g F_{cr}} < 1.00$ | (kL/r) _x =52 (kL/r) _y =82 | Pu = 1.02 Ag = 1.44 Fcr = 25.30 | 0.03 |
| Lateral Torsional Buckling (F10-2,3) | $\frac{M}{0.9M_n} < 1.00$ Critical Segment from 0.00 to 4.05 on -z flange Segment End Moments: 0.00 and 0.00 | Lb = 4.05 Cb = 1.14 | M = 0.01 Mn = 2.34 Me = -1.00 | 0.01 |
| Combined Forces (compress.) (H1-1b) | $\frac{P_r}{2\phi P_n} + \frac{M_{rx}}{\phi M_n x} + \frac{M_{ry}}{\phi M_n y} < 1.00$ | Cmx = 1.00 Cmy = 1.00 Pex = 153.11 Pey = 61.57 | Mrx = 0.01 Mry = 0.02 B1x = 1.01 B1y = 1.02 | 0.03 |

Detailed Results Table for Beam 3

Moments: kips*foot , Forces: kips , Stresses: ksi , Section prop.: inch



CONSTRAINTS

- Sections : Check
 - Steel Grade: A36

DESIGN DATA

- Kx = 1.00 - Ky = 1.00
 - Allow. Slend. : 200 (compr.) 300 (tens.)
 - Allowable Deflection : 1/240
 - Tension Area Reduction Factor : 1.00
 - Building type : Unbraced

Cedar St WT Ashland MA

Code: AISC-LRFD

Prepared by:

Date: 5/14/18

Detailed Results Table for Beam 3


Moments: kips*foot , Forces: kips , Stresses: ksi , Section prop.: inch

Section: L 3x3x1/4

$I_x = 1.24$ $I_y = 1.24$ $I_{x^2} = 0.58$ $I_{y^2} = 0.58$ $I_{xy} = 1.44$
 $h = 3.00$ $b = 3.00$ $t = 0.25$ $e_y = 2.15$ $e_x = 2.15$
 $J = 0.03$ $C_w = 0.00$ $I_v = 0.50$ $I_{v^2} = 0.50$


DESIGN COMBINATION = 2

M2 Moment Diagram



Max. AXIAL Force = 1.02 (tens.) Max. SHEAR Force = 0.01

M3 Moment Diagram





Max. AXIAL Force = 1.02 (tens.) Max. SHEAR Force = 0.01

SECTION CLASSIFICATION: *** COMPACT ***

| Limiting Ratios: | Compact | Non-Compact | Slender -axial | |
|------------------|---------|-------------|----------------|------------------|
| $d/t = 12.10$ | < 15.3 | 25.8 | 12.8 | ($F_y = 36.0$) |
| $b/t = 12.10$ | < 15.3 | 25.8 | 12.8 | |

| DESIGN | EQUATION | FACTORS | VALUES | RESULT |
|--------------------------------------|--|------------------------------------|---|--------|
| M3 Moment (F10-1) without LTB | $\frac{M}{0.9M_n} < 1.00$ | $Z = 0.58$ | $M = 0.01$ $M_n = 2.60$ | 0.01 |
| M2 Moment (F10-1) without LTB | $\frac{M}{0.9M_n} < 1.00$ | $Z = 0.58$ | $M = 0.01$ $M_n = 2.60$ | 0.01 |
| Axial Force (D2-1) | $\frac{P_u}{0.9A_g F_y} < 1.00$ | $(kL/r)_x = 52$ $(kL/r)_y = 82$ | $P_u = 1.02$ $A_g = 1.44$ $F_y = 36.00$ | 0.02 |
| Lateral Torsional Buckling (F10-2,3) | $\frac{M}{0.9M_n} < 1.00$ Critical Segment from 0.00 to 4.05 on -z flange Segment End Moments: 0.00 and 0.00 | $L_b = 4.05$ $C_b = 1.14$ | $M = 0.01$ $M_n = 2.34$ $M_e = -1.00$ | 0.01 |
| Combined Forces (tension) (H1-1b) | $\frac{P_r}{2\phi P_n} + \frac{M_{rx}}{\phi M_n x} + \frac{M_{ry}}{\phi M_n y} < 1.00$ | | $M_{rx} = 0.01$ $M_{ry} = 0.01$ | 0.02 |




STUD WELD DESIGN FOR VERTICAL LOAD:


Assume 8 studs in Shear, 2 Studs in Tension

$V_{stud} = 420\text{lbs} / 8\text{studs}$
 $V_{stud} = 52.5\text{lbs} \ll [T_{max} = 2397\text{lbs from Nelson Table}], \text{OK}$
 $S.F. = 2397 / 52.5$
 $S.F. = 45.6$

$T_{stud} = (420\text{lbs} \times 12\text{in}) / (9 \times 2); \text{ on 2studs}$
 $T_{stud} = 280\text{lbs} \ll [T_{max} = .6F_y \times A_{stud}]$
 $T_{stud} = 280\text{lbs} \ll [T_{max} = .6 \times 50,000 \times .0522]$
 $T_{stud} = 280\text{lbs} \ll [T_{max} = 1566\text{lbs}], \text{OK}$
 $S.F. = 1566 / 280$
 $S.F. = 5.6$



BY INSPECTION AND COMPARISON TO THE VERTICAL LOAD VALUES AND GEOMETRY, THE HORIZONTAL LOAD DOES NOT GOVERN THE DESIGN OF THE EXISTING STUDS.



PROPOSED STUD WELD DESIGN CHECK:

Assume 4 studs in Shear, 2 Studs in Tension
Use X1=780lbs for shear value and Tension value (cons.)

$V_{stud} = 780\text{lbs} / 4\text{studs}$
 $V_{stud} = 195\text{lbs} \ll [T_{max} = 2397\text{lbs from Nelson Table}], \text{OK}$
 $S.F. = 2397 / 195$
 $S.F. = 12.3$

$T_{stud} = (780\text{lbs} \times 3.5\text{in}) / (4 \times 2); \text{ on 2studs}$
 $T_{stud} = 341\text{lbs} \ll [T_{max} = .6F_y \times A_{stud}]$
 $T_{stud} = 341\text{lbs} \ll [T_{max} = .6 \times 50,000 \times .0522]$
 $T_{stud} = 341\text{lbs} \ll [T_{max} = 1566\text{lbs}], \text{OK}$
 $S.F. = 1566 / 341$
 $S.F. = 4.6$

General Information for Stud Welding Studs

Standard Arc Welding Studs – Tensile and Torque Strengths

Mild Steel – 61,000psi Minimum Ultimate, 50,000 psi Minimum Yield

| Thread Diameter | META ¹ (sq. in.) | Yield Load (lbs.) at 50,000 psi | Ultimate Tensile Load (lbs) at 61,000 psi | Yield Torque ² (ft-lbs) at 50,000 psi | Ultimate Torque (ft-lbs) at 61,000 psi | Shear Strength ³ (75% of Tensile Strength) |
|-----------------|-----------------------------|---------------------------------|---|--|--|---|
| 10-24 UNC | 0.0174 | 870 | 1,061 | 2.7 | 3.3 | 796 |
| 10-32 UNF | 0.0199 | 1,000 | 1,220 | 3.1 | 3.8 | 915 |
| | | | | | | |
| 1/4-20 UNC | 0.0317 | 1,590 | 1,940 | 6.6 | 8.1 | 1,455 |
| 1/4-28 UNF | 0.0362 | 1,810 | 2,208 | 7.5 | 9.2 | 1,656 |
| | | | | | | |
| 5/16-18 UNC | 0.0522 | 2,620 | 3,196 | 13.6 | 16.6 | 2,397 |
| 5/16-24 UNF | 0.0579 | 2,895 | 3,532 | 15.1 | 18.4 | 2,649 |
| | | | | | | |
| 3/8-16 INC | 0.0773 | 3,875 | 4,728 | 24.2 | 29.5 | 3,546 |
| 3/8-24 UNF | 0.0876 | 4,380 | 5,344 | 27.4 | 33.4 | 4,008 |
| | | | | | | |
| 7/16- 14 UNC | 0.1060 | 5,315 | 6,484 | 38.7 | 47.2 | 4,863 |
| 7/16-20 UNF | 0.1185 | 5,900 | 7,198 | 43.0 | 52.4 | 5,399 |
| | | | | | | |
| 1/2-13 UNC | 0.1416 | 7,095 | 8,656 | 59.1 | 72.1 | 6,492 |
| 1/2-20 UNF | 0.1597 | 8,000 | 9,760 | 66.7 | 81.3 | 7,320 |
| | | | | | | |
| 5/8-11 UNC | 0.2256 | 11,300 | 13,786 | 117.7 | 143.6 | 10,340 |
| 5/8-18 UNF | 0.2555 | 12,750 | 15,555 | 132.8 | 162.0 | 11,666 |
| | | | | | | |
| 3/4-10 INC | 0.3340 | 16,700 | 20,374 | 208.8 | 254.7 | 15,281 |
| 3/4-16 UNF | 0.3724 | 18,600 | 22,692 | 232.5 | 283.7 | 17,019 |
| | | | | | | |
| 7/8-9 UNC | 0.4612 | 23,100 | 28,182 | 336.9 | 411.0 | 21,137 |
| 7/8-14 UNF | 0.5088 | 25,450 | 31,049 | 371.1 | 452.8 | 23,287 |
| | | | | | | |
| 1-8 UNC | 0.6051 | 30,300 | 36,966 | 505.0 | 616.1 | 27,725 |
| 1-14 UNF | 0.6791 | 33,900 | 41,358 | 565.0 | 689.3 | 31,019 |

* Torque figures based on assumption that excessive deformation of thread has not taken relationship between torque/tension out of its proportional range.

In actual practice, stud should not be used at its yield load. A factor of safety must be applied. It is generally recommended that studs not be used at more than 60% of yield strength, however, the factor of safety may vary up or down according to the particular application in which the studs are being used.

The user of these studs will make this determination

Formulae used to make the above calculations are as follows:

| | | | |
|------------------|----------|-----------------|-----------------------------|
| Ultimate Tensile | $L = SA$ | Ultimate Torque | $T = 0.2 \times D \times L$ |
| Yield | $Z = YA$ | Yield Torque | $T = 0.2 \times D \times Z$ |

Where

| | |
|-----------------------------|---------------------------------------|
| D = Nominal Thread Diameter | A = Mean Effective Thread Area (META) |
| S = Tensile Stress (psi) | Y = Yield Stress (psi) |
| L = Tensile Load (lbs) | Z = Yield Load |

T = Torque (in-lbs)

- 1 META is used instead of root area in calculating screw lengths because of closer correlation with actual tensile strength. META is based on mean diameter, which is the diameter of an imaginary co-axial cylinder whose surface would pass through the thread profile approximately midway between the minor and pitch diameters.
- 2 In actual practice, stud should not be used at its yield load. A factor of safety must be applied. It is generally recommended that studs not be used at more than 60% of yield strength, however, the factor of safety may vary up or down according to the particular application in which the studs are being used.

The user will make this safety factor determination

- 3 Shear values are based on Tensile Strength of the stud.



